

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 39 N.R. 18 W.


Delta COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 29, 30, 31, 32

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9/20/60 with Frank J. Bray.

WITNESSES TO CORNER.....16" W. Pine (S 31 NBT) N 51° W 73 Links



14" Red Pine (S 30 NBT) S 40° W 90½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by proportionate distance west to Section corner 1 mile; east to line tree 49.45 chains, and south to Section corner 1 mile. Found no evidence of original corner. Corner lies 03 links south of new E-W fenceline.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 5/31/61
REGISTERED LAND SURVEYOR
Billy D. Buckler