

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


DELTA COUNTY  
T 39 N R 18 W

DESCRIPTION OF CORNER Section corner for  $\frac{3}{2}$   
10/11

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED November 24, 1971

WITNESSES TO CORNER..... 9" Cedar (S.3) (NBT) N54°W, 25.2'



7" W. Birch (S.10) (NBT) S10°W, 24.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by double proportionate measure from the corners  
1 mile north, 1 mile south,  $\frac{1}{2}$  mile east and the spring west 72.25 by government  
notes.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Frank J. Bray*  
REGISTERED LAND SURVEYOR  
Frank J. Bray

DATE

1-7-72

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68