

JAN 25 2000

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On Dec 28, 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Walter C. Thomas*  
Chairman

For corners in

DELTA (County)	Located In:	Corner Code #
1. Public Land Survey	T <sup>39</sup> N R <sup>19</sup> W	J-12
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

RECORDED 01-04-00  
AT 2:00 O'CLOCK P.M.  
LIBER 9 PAGE 164  
*Walter C. Thomas*  
COUNTY CLERK

Register of Deeds Stamp & File Number

J-12 [C1/4 COR SEC 35]

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, M.P. DAVIS, in a field survey on DECEMBER, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-12 [C1/4 COR SEC 35] NOT SET IN ORIGINALS  
NO RECORD EVIDENCE OF PREVIOUS MONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-12 [C1/4 COR SEC 35] ESTABLISHED CORNER POSITION AT THE INTERSECTION OF THE N-S AND E-W QUATER LINES OF THE SECTION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-12 SET A 5/8" X 18" REBAR W/A 3-1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.

MAPLE 11"	MAPLE 18"	FENCE LINE SOUTH	OLD E-W FENCE	NEWER E-W FENCE	NOTE: FARM FIELDS
S70°W	S20°E	EAST	SOUTH	SOUTH	IN ALL 4
4.90'	5.65'	55.0'	4.0'	10.5'	QUADS.



NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/10/99  
Surveyor's Michigan License No. 16926