

JAN 6 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On Dec 28, 1999

Robert Schmeling
Acting Chairman

For corners in

Table with columns: DELTA (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number. Includes handwritten file number 0104-00, time 2:00 O'CLOCK PM, page 9, and signature of William C. Thomas.

4. Lot No. , Recorded Plat
5. Private Claims

I, M.P. DAVIS, in a field survey on NOVEMBER, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

A-13 [SW COR SEC 31] JOHN BURT, D.S.-1845-WOOD POST (BEECH 10" S50°W 34 LINKS)(BEECH 10" N82°E 29 LINKS M.S.McNABB-1916-ID FROM ORIGINALS. NO DESCRIPTION OF MONUMENT FOUND OR NEW BT'S NOTED. BILLY D. BUCKLER-1961-NO CORNER EVIDENCE FOUND-REESTABLISHED CORNER POSITION BY DOUBLE PROPORTIONATE DISTANCE BETWEEN CORNERS 1 MILE WEST, NORTH & SOUTH AND SECTION CORNER 2 MILES EAST. SET 1" I.P. W/A 4" BRASS CAP STAMPED TO ID THE CORNER POSITION, FROM WHICH A 12" W.PINE N78°E 05 LINKS-H.MAPLE 14" S41°W 13 LINKS-H.MAPLE 8" S20°E 45 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 [SW COR SEC 31] FOUND IN PLACE A 1" I.P. W/A 4" BRASS CAP STAMPED TO ID THE CORNER POSITION. ID SAME AS THAT BEING SET IN 1961 BY BILLY D. BUCKLER FROM HIS SW BT WHICH IS STILL GREEN AND NE BT WHICH IS A 3' HIGH STUMP WITH IRON MARKS STILL PLAIN ON THE LOWER BLAZE. ACCEPTED AS BEING A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 DID NOT DISTURB EXISTING MONUMENT AND NOTED NEW BT'S
MAPLE 09" MAPLE 07" MAPLE 07" MAPLE 17" (OLD BT)
N82°W N42°E S33°E S45°W
16.70' 24.17' 10.18' 09.24'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/20/99
Surveyor's Michigan License No. 16926