

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>34</u> T. <u>39</u> N. S., R. <u>19</u> E. W.		<u>H-12, G-12M.C.</u>
2. PROPERTY CONTROLLING IN SECTION <u>34</u> T. <u>39</u> N. S., R. <u>19</u> E. W.		<u>11</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**DELTA
CO.**

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 5 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

H-12 Center of Section; none of record

G-12 M.C. M.C. on W. line of Sec. 34; Wood Post - original corner bearing trees - cedar 10" - S25°W - 30 links; balsam 5 - S45°E - 11 links. Bearings to island - northend N33°W - southend N50½°W

11 1/16 corner - center of S.W.¼ of Sec. 34; none of record

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-12 Set at intersection of N-S and E-W ¼ lines. West ¼ cor. falls in lake, therefore, the E-W line was established using the E¼ cor. and a mean bearing of the north Sec. line and the south sec. line. A 1 3/4" x 3/8" iron bar was found buried in the road 16.26 ft. south of this point. It is not of record and was obviously set at mid point on the N-S ¼ line without regard to the E-W line. Therefore, it was not accepted as being the true corner.

G-12 M.C. - Set mon. from 17" cedar which is original bearing tree both faces visible but badly weathered.

11 - Set at computed center of the S.W. ¼ of Sec. 34 - A 3/4" iron rod was found 9.7' S.E. of this point. It is not of record & was apparently set in relation to an erroneous ctr. of sec. marker.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ALL - 1" pipe, 4" aluminum cap.

H-12 - Fence post - S73°E - 28.5'; 4" apple tree - N83°E - 25.2'; 6" apple tree - N16°E - 94.2'; 1 3/4" x 3/8" iron bar buried in road - south - 16.26'

G-12 M.C. 9" cedar - S52°E - 10.9'; 13" cedar - S72°E - 33.3'; 17" cedar - S25°W - 20.3' "O.B.T." 10" cedar - S67°W - 90.8'

11 - Pine post; ^{SET BESIDE MONUMENT} 3" apple tree - S86°E - 23.7' (not marked); 7" apple tree - S3°E - 84.5'; 3" W. ash - S25°E - 57.5' (not marked); 3/4" iron rod - S36°E - 9.7'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ 21558