

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	33 T. 39 N. 1/4, R. 19 W.	E-13-M.C.
2. PROPERTY CONTROLLING IN SECTION	33 T. 39 N. 1/4, R. 19 W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	33 T. 39 N. 1/4, R. 19 W.	9-A
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA
CO.

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 12 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-13-M.C. - Point on township line. D.N.R. Mon. was set 63.2' west of this position but was destroyed - probably by tourists from Fayette State Park. 9" cedar - S66°E - 13.5'; 9" cedar - N50°E - 20.0'
- 16 - E 1/16 corner on south section line; not previously established.
- 9-A - Point on N-S 1/16 line in S.E. 1/4 of Sec. 33 about 25' south of the high water mark on Lake Michigan shore; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-13-M.C. - Set new meander corner on twp. line 63.2' east of B. Bucklers M.C. which has been destroyed - his N.B.T.S still in place but would put the mon. right in a scenic over look spot on the Bluff - I set it east to avoid the probability of destruction by tourists.
- 16 - Set M.P.O.L. between the S 1/4 cor. and the S.E. sec. cor. of Sec. 33
- 9-A - Established N-S 1/16 line parallel with the east sec. line - set mon. on said 1/16 line near its intersection with the shore of Lake Michigan. 2025.8' north of E 1/16 cor. on the S. Sec. line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-13-M.C. - 6" Cedar - N28°W - 11.35'; 10" cedar - S86°W - 8.8'; 6" cedar - S07°E - 13.6'; 6" cedar - S67°E - 2.45'
- 16 - 6" ironwood - West - 20.3'; 5" ironwood - N40°E - 32.8'; 8" ironwood - S15°E - 39.4'; 8" h. maple - S50°W - 45.1'
- 9-A - 16" cedar - S45°E - 4.4'; 7" cedar - N07°E - 13.85'; 14" cedar - S49°W - 69.9'; 7" cedar - S5°W - 34.3'

ALL 1" PIPE, 1" ALUMINUM CAP — E-13-M.C. IS SET IN CONC.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558