

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>39</u> N. S., R. <u>19</u> E. W.		<u>H-11, I-11, I-10</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

*DELTA  
CO.*

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Pabbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on September 29 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- H-11 - South  $\frac{1}{4}$  corner; "wood post" - original corner bearing trees; Beech 5" - S70°W - 1 $\frac{1}{4}$  links; sugar 2 $\frac{1}{4}$ " - N71°E - 6 links.
- I-11 - S.E. section corner. "Wood post" - original corner bearing trees; beech 7" - S55°W - 19 link  
Beech 5" - N65°E - 10 links.
- I-10 - E  $\frac{1}{4}$  corner; "Wood post" - original bearing trees: none available

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- H-11 - Found 3/4" pipe in centerline of N-S road in line with old fence west (not of record).
- I-11 - Set by double prop. mea. using  $\frac{1}{4}$  cors.  $\frac{1}{2}$  mile in each direction.
- I-10 - Found 3/4" iron rod in old E-W fence line (not of record). Fits occupation and G.L.O. calls to stream well.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- ALL - 1" pipe, 4" aluminum cap.
- H-11 - D.N.R. Mon. buried in road; 12" stem of tw. W. birch - S20°E - 84.6'; 8" scotch pine - N48°E - 62.55'; 6" scotch pine - N26°E - 53.3'; 2" apple - N88°W - 62.6' (not marked).
- I-11 - Cedar post; <sup>SET BESIDE MONUMENT 26.</sup> 11" hemlock - N40°E - 26.8'; 11" cedar - S57°E - 85.9'; 12" cedar - S12°W - 24.9'; 8" cedar - N70°W - 38.8'
- I-10 - Cedar post; <sup>SET BESIDE MONUMENT 26.</sup> 8" cedar - S33°E - 145.4'; 6" cedar - S60°E - 134.4'; 7" cedar - N89°E - 142.8'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558