

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

| FOR CORNERS OF--                           | LOCATED IN--                           | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY _____                | T. <u>39</u> N. S., R. <u>19</u> E. W. | J-11, K-11, I-12   |
| 2. PROPERTY CONTROLLING IN SECTION _____   | T. _____ N. S., R. _____ E. W.         | _____              |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S., R. _____ E. W.         | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____      |  |                    |
| 5. PRIVATE CLAIMS _____                    |  |                    |

DELTA  
CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Eabbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 28 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- J-11 - North  $\frac{1}{4}$  cor. monument - not described in records. McNabb corner of 1917 on road traverse - moving west. Fence right 29.5'; fence left 36.0'; w. birch 8" - N8<sup>o</sup>W - 54.0"; telephone pole - S3<sup>o</sup>E - 30.9'; 2634.97' west of section corner of sections 25, 26, 35 and 36.
- K-11 - N.E. section corner. McNabb corner of 1917 on road traverse - moving north. Iron pin in center line of road intersection, Old Bts. maple 3" - N57<sup>o</sup>E - 32.4'; w. birch 6" - S42<sup>o</sup>W - 49.4'; newer Bts. - soft maple 9" - S48<sup>o</sup>W - 50.0'; power pole - N20<sup>o</sup>E - 81.7'
- I-12 - West  $\frac{1}{4}$  corner. "Wood post" - original corner bearing trees; Beech 16" - S34<sup>o</sup>W - 32 links; beech 9" - N35 E - 20 links.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- J-11 - Set in line with old fence north and 36' north of old E-W fence along the south side of Co. Rd. as described in old notes by M. McNabb dated 1916. Also fist McNabb's recorded distance to corner of Sec. 35. Falls 9' south of centerline of existing blacktop county road.
- K-11 - Set from old M. McNabb northeast N.B.T. - his iron and other N.B.T.'s destroyed by road construction.
- I-12 - Set in line with old stone fence east and centerline of road south and in old cedar post fence north.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- J-11 - 1/2" pipe & plastic R.L.S. cap; face of power pole - S77<sup>o</sup>E - 140.3'; 10" stem of tw. cedar - N21<sup>o</sup>E - 81.2'; S.W. cor. of house foundation - N41<sup>o</sup>W - 98.7'; NE cor. of house foundation - N17<sup>o</sup>W - 115.4'.
- K-11 - 1" pipe, 4" aluminum cap buried in road int.; 6" cedar - S69<sup>o</sup>W - 90.4'; nail & cap in side of power pole - S17<sup>o</sup>E - 83.45'; 5" cedar - S70<sup>o</sup>E - 68.7'; 6" cedar - N38<sup>o</sup>E - 92.9'.
- I-12 - 1" pipe, 4" aluminum cap; 5" r. pine - N28<sup>o</sup>E - 52.5'; 4" r. pine - N82<sup>o</sup>E - 25.1'; 6" apple S10<sup>o</sup>W - 102.5'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES: \_\_\_\_\_

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558