

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Delta</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>39N</u> R <u>19W</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

49

Register of Deeds Stamp & File Number

I, David B. Babbitt, in a field survey on 3/17, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-11. NE section corner of Section 35. Marcus McNabb, 1946, set iron from BTs set previously.
Soft Maple 9", S48W - 50'
Power Pole, N20E - 81.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11. In 1977 I made a search for McNabb's iron but for some reason (perhaps because we were still using a dip needle at that time), I did not find it. I did, however, find the cut off bottom of the power pole which McNabb had used as a witness and recorded as N20E, 81.7'. His soft maple NBT was gone. Having found no iron I proceeded to set a DNR monument using McNabb's bearing and distance to the power pole for control. This position fell in line with RD. Centerlines N-S&W and measurements to other known survey monuments in the area looked reasonable. In 1986, Bowman Land Surveying, Inc. of Gulliver, Michigan, made a survey in the NW1/4 of Section 36 which was a retracement of a 1946 survey by McNabb. By comparing his measurements they located a small iron pin which fit McNabb's measurement to the power pole N20E, 81.7' but differs slightly by bearing from the monument I had set. Since the found iron appears to be McNabb's corner marker, my DNR monument has been moved to the position of the found iron and witnesses taken accordingly.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11. DNR Monument (buried)
Face of Blaze on 7" cedar, S65E, 73.7'
" 6" cedar, N40E, 94.2'
Tag in 7" w.birch, N50E, 66.13'
" 6" cedar, S65W, 90.05'
" power pole, S20E, 86.52'

Signed by David B. Babbitt

Date 3-23-1987

Surveyor's Michigan License No. 21558