

REMONUMENTATION

FEB 22 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 10/26, 1995  
Mike Davis RLS  
Chairman

For corners in

Delta

(County)

Located In:

Corner Code #

- |                                    |   |            |   |            |     |
|------------------------------------|---|------------|---|------------|-----|
| 1. Public Land Survey              | T | <u>39N</u> | R | <u>21W</u> | D-2 |
|                                    | T |            | R |            |     |
|                                    | T |            | R |            |     |
|                                    | T |            | R |            |     |
| 2. Property Controlling in Section | S |            | T |            | R   |
|                                    | S |            | T |            | R   |
| 3. Miscellaneous Property in Sec.  | S |            | T |            | R   |
|                                    | S |            | T |            | R   |

Recorded Oct 27 1995  
at 9:00 o'clock AM in Liber 8 Page 103  
Walter C. Thorne Reg. of Deeds.  
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			•		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Robert E. Schmeling, in a field survey on October 19, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Center  $\frac{1}{4}$  corner, Section 5, T39N, R21W which was not set in the original survey of Michigan. Harold Y. Stockholm, U.S.F.S., RLS 23519, on May 13, 1980 found no evidence that corner had been previously established. He established corner by section subdivision survey and set at intersection of straight lines between the opposite quarter corners on the perimeter of Section 5. He set a  $2\frac{1}{2}$ " diameter by 4' long concrete filled galvanized iron pipe 31" in ground; capped with a 3" diameter brass cap stamped to identify corner(found in place this date). He made, blazed, scribed "BT", tagged, and painted witnesses: Maple 12" S44E 22.9 feet(still alive standing tree) and Maple 9" S48W 14.5 feet(still a live standing tree). He set a 4"x4" cedar post 3.1' west of monument with a sign attached(found in place). All his measurements to E of tree and nail and to E of post. His report filed October 30, 1981 in L.5, P.62 of Survey Records, Register of Deeds.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Accepted above monument as the best available evidence of the position of the corner and further improved accessories a/w P.A.345 of Public Acts of 1990.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Witnesses found in place:

Hard Maple 12" S44E 22.9 feet to E of tree and nail(Scribed: BT)

Hard Maple 9" S48W 14.5 feet to E of tree and nail(Scribed: BT)

New witnesses made:

Hard Maple 14" N88E 16.4 feet to E of tree and PK nail(Scribed: C $\frac{1}{4}$  NBT)

Hard Maple 9" N70W 38.0 feet to E of tree and PK nail(Scribed: C $\frac{1}{4}$  NBT)

Placed iron post 2' nw of monument with warning tag bolted thereon. Placed bearing tree tags on back side of all four witness trees. All bearings are magnetic.

Signed by Robert E. Schmeling  
Surveyor's Michigan License No. \_\_\_\_\_

Date October 20, 1995

8317