

REMONUMENTATION

FEB 22 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 10/20, 1995  
Walter C. Thum  
Chairman

For corners in

| Delta County<br>(County)              | Located In:             | Corner Code ## |
|---------------------------------------|-------------------------|----------------|
| 1. Public Land Survey                 | T 39N R 21W             | E-2            |
|                                       | T _____ R _____         | _____          |
|                                       | T _____ R _____         | _____          |
|                                       | T _____ R _____         | _____          |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____          |
|                                       | S _____ T _____ R _____ | _____          |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____          |
|                                       | S _____ T _____ R _____ | _____          |

Recorded Oct 27 1995  
at 9:00 o'clock AM in Liber 8 Page 104  
Walter C. Thum Reg. of Deeds.  
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

Robert E. Schmeling, in a field survey on October 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

$\frac{1}{4}$  corner between Sections 4 and 5, T39N, R21W originally set by Deputy Surveyor A. Merryweather in 1848: a wood post witnessed by Cedar 9 S8W 50 links (In 1957 a charred upturned stump with upper face visible and showing old axe marks, the scribing eroded away) and B. Ash 12 N21E 48 links (In 1957 no evidence remaining).

On November 5, 1957 Robert E. Schmeling placed  $1\frac{1}{2}$  galvanized iron pipe with brass cap after identifying original cedar noted above and locating point of wood stake at record distance from witness. He made new witnesses: White Cedar 5" N68W 86 links (now a down dead bole), Balsam Fir 8" N12E  $11\frac{1}{2}$  links (now a cut stump) and Aspen 7" S32E  $26\frac{1}{2}$  links (now a cut stump). Recorded L.3, P.66 of Land Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Glen Bergey, RLS 19827 on October 17, 1972 (recorded L.1, P.547) made added witnesses: Elm 12" N61E 25.08 feet (now a cut stump), Balsam Fir 7" S11W 19.14 feet (now a dead 30' high stub), and a Cedar 7" N36W 52.14 feet (now down and dead).

Found in place  $1\frac{1}{2}$ " pipe with brass cap with identification thereon. Found an additional witness: to above placed by U.S.F.S. in May, 1980, but not recorded in Delta C. Reg. of Deeds Office: Cedar 13" N73E 63.5 feet (now a live standing tree, blazed at base and scribed "NBT") and Cedar 10" N68W 56.7 feet (now down and dead).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Left in place  $1\frac{1}{4}$  x 4" galvanized iron pipe with brass cap set in 1957 and is accepted as a careful and faithful perpetuation of the position of the original corner. Made new witnesses:

White Cedar 13" N73E 63.5 feet to E of tree & PK nail (same described above)

Balsam Fir 7" S49W 11.15 feet to E of tree & PK nail (Scribed:  $\frac{1}{2}$ S5 NBT)

Yellow Birch 12" N44W 37.68 feet to E of tree & PK nail (Scribed:  $\frac{1}{2}$ S5 NBT)


White Cedar 9" N27W 53.80 feet to E of tree & PK nail (Scribed:  $\frac{1}{2}$ S5 NBT)

Placed steel fence post with warning tag 2.0 feet N45W of corner monument. "BT" tags placed breast high on each witness tree. All bearings are magnetic.

Signed by Robert E. Schmeling  
Robert E. Schmeling

8317

Date October 19, 1995



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983