

COMMISSION
REMONUMENTATION

FEB 22 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 10/26, 1995
McGowan RLS
Chairman

For corners in

<u>Delta</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>39N</u> R <u>21W</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded Oct 27 1995
at 9:00 o'clock AM in Liber 8 Page 105
Wallace C. Thomas Reg. of Deeds.
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

Robert E. Schmeling, in a field survey on October 19, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Section corner common to Sections 4, 5, 8, and 9, T39N, R21W as established by A. Merryweather in 1848: He set a wood post and bearing trees: Birch 14 N22E 26 links(no evidence remaining) and Sugar 16 S44W 58 links(no evidence remaining)

County Surveyor, Marcus McNabb, assisted by Clarence E. Rose, on November 17, 1914 recovered the original Sugar bearing tree as a down tree and from this perpetuated the corner. He set stake and bearing stakes NE and SW at 33 feet from corner. See Page 144 of Delta County Survey Record Book No.1(old book). The corner was later marked by a 5' long x 3/4" diameter solid iron rod set 4' in ground by unknown person.

Harold Y. Stockholm, U.S.F.S, RLS 23519, on July 17, 1979 restored above corner. He found the above iron rod and a 3"x3' long wood post on ground with an Escanaba Paper Co. locator tag thereon

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(latter set by R. Schmeling in 1957, who then also observed the iron rod and a corner standing fence post and wire at the location)(in 1995 fence post down and in duff). Stockholm replaced iron rod with a 2 1/2" diameter x 4' long concrete filled galvanized iron pipe set 3' in ground, capped with a 3" diameter brass cap stamped to identify corner. The old rod placed alongside new monument. He blazed, tagged, scribed "BT", and painted following witness trees:

- (Hard)Maple 8" S72E 26.65 feet to E of tree and nail(Scribed: BT)
- (Hard)Maple 14" N32W 62.70 feet to E of tree and nail(Scribed: BT)
- (Basswood)Maple 11" S54W 44.50 feet to E of tree and nail(Scribed: BT)
- Hop Hornbean 9" N06W 33.20 feet to E of tree and nain(Scribed: BT)

Stockholm set a 4"x4" cedar post with warning tag west 2.6 feet. He filed a report November 24, 1980 with register of Deeds in L.2, P.442.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted the above monument and accessories as a careful and faithful perpetuation of the original corner and made the following improvements a/w P.A.345 of the Public Acts of 1990.
Placed a steel fence post with warning tag thereon 2' NW of corner monument.Placed bearing tree tags head high on back side of the four witness trees.

Signed by Robert E. Schmeling Date October 20, 1995
Surveyor's Michigan License No. 8317