

Approved By Delta County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 of  
 P.A. Of 1990 On 12/22, 2000  
*Robert R. Kelmeling*  
 Acting Chairman

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA (County)	Located In:	Corner Code #
1. Public Land Survey	T <sup>39</sup> N R <sup>23</sup> W	B-05
	T <sup>39</sup> N R <sup>23</sup> W	B-06 ✓
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED 08 January 2001  
 AT 9:00 O'CLOCK A.M.  
 LIBER 9 PAGE 247  
*Marcy G. Kolich*  
 DELTA COUNTY M. REG. OF DEEDS

Register of Deeds Stamp & File Number

B-05 [N1/4 COR SEC 18] B-06 [C1/4 COR SEC 18]

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, M.P. DAVIS, in a field survey on DECEMBER, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	●												
6	●	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-05 [N1/4 COR SEC 18] A.MERRYWEATHER, D.S.-1846-WOOD POST-(SPRUCE 04" S20°W 08 LINKS)(TAMERAC 04" S42°E 10 LINKS) M.S.McNABB-1918-ID CORNER POSITION FROM ORIGINALS-SET WOOD POST SCRIBED 1/4" (TAMERAC 03" S45°E 15')(CEDAR 05" N60°W 17.6')

B-06 [C1/4 COR SEC 18] NOT SET IN ORIGINALS  
 M.S.McNABB-1918-SET STAKE AT INTERSECTION OF 1/4 LINES (TAMARACK 18" WEST 8.3')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-05 [N1/4 COR SEC 18] NO CORNER EVIDENCE FOUND AS THE AREA APPEARS TO HAVE BEEN GREATLY DISTURBED DURING LOGGING OPERATIONS. RECOVERED McNABB'S C1/4 COR AND S1/4 COR OF SEC 18 AND EXTENDED A LINE NORTH FROM THE S1/4 COR THRU THE C1/4 COR AND REESTABLISHED THE N1/4 COR ON THIS LINE AND AT A PROPORTIONATE DISTANCE NORTH OF THE C1/4 COR. THE PROPORTIONATE DISTANCE BEING BASED ON THE 1918 DISTANCES OF McNABB, WHICH CHECK VERY CLOSELY WITH HIS MEASUREMENTS. ACCEPTED AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

B-06 [C1/4 COR SEC 18] FOUND IN PLACE A POST POINT. ID SAME AS THAT BEING SET BY McNABB FROM THE REMAINS OF HIS TAMARACK BT TO THE WEST, NOW ONLY A BADLY DETERIORATED STUMP, NO IRON MARKS VISIBLE, AND A COMPARISON OF HIS MEASUREMENT TO THE FOUND CS1/16 AND THE FOUND E1/4 COR WHICH CHECK VERY WELL WITH THE RECORD DISTANCE OF McNABB. THE POST POINT WAS FOUND TO BE 0.75' NORTH OF A DIRECT LINE BETWEEN THE E & W 1/4 COR'S. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL ESTABLISHMENT OF THE CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-05 SET A BERNTSEN A1NB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.  
 CEDAR 08" CEDAR 09" CEDAR 06" CEDAR 07" SURVEY MONUMENT SIGN POST  
 N28°W N61°E S66°E. S64°W NORTH  
 33.22' 29.38' 34.50' 12.53' 0.92' (TO FACE)

B-06 REPLACED POST POINT WITH A BERNTSEN A1NB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.  
 CEDAR 10" CEDAR 06" CEDAR 07" CEDAR 08" SURVEY MONUMENT SIGN POST  
 N12°W N15°E N65°E N74°W SOUTH  
 27.81' 15.32' 4.27' 14.03' 1.28' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis  
 Surveyor's Michigan License No. 16926

Date 12/23/00

