

SURVEY & REMONUMENTATION

DEC 07 1993

COMMISSION

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On November 30, 1993

Robert Schumling
Acting Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|-----------------------------|----------------------|
| 1. Public Land Survey | T <u>39 N</u> R <u>23 W</u> | <u>B-7 & C-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

DELTA COUNTY

LIBER 7 PAGE 341

93 DEC -2 AM 9:00

William C. Thayer
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
B-7 [1/4 COR COMMON TO SEC'S 18/19] C-1 [NW COR SEC 5]

I, M.P. DAVIS, in a field survey on MAY 1993, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- B-7 [1/4 COR COMMON TO SEC'S 18/19] WOOD POST-1846-A.MERRYWEATHER D.S. (IRONWOOD 10"-N50°E-14 LINKS) (SUGAR MAPLE 20"-S23°W-16 LINKS) M.S. McNABB - 1914 - NO EVIDENCE OF ORIGINALS FOUND - ESTABLISHED BETWEEN CORNERS SET IRON STAKE - FENCE POST S76°30'W 44.8'
- C-1 [NW COR SEC 5] WOOD POST-1844-JOHN BURT D.S. (HEMLOCK 14"-N75°E-27 LINKS) (Y.BIRCH 16"-N49°W-24 LINKS) A.MERRYWEATHER D.S. - 1846 - (HEMLOCK 14"-S24°E-17 LINKS) (HEMLOCK 7"-S20°W-4 LINKS) C.E. BROTHERTON - 1884 - ORIGINALS IN PLACE - NO NEW WIP'S NOTED M.S. McNABB - 1914 - ID FROM REMAINS OF ORIGINAL BT - BT STAKES NE & SW 33' M.S. McNABB - 1919 - SET IRON STAKE - BT STAKES IN PLACE M.DAVIS -1977 - L.C.R.'S. IN LIBER 2 PAGE 147

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-7 [1/4 COR COMMON TO SEC'S 18/19] McNABB'S IRON STAKE APPARENTLY DESTROYED IN ROAD CONSTRUCTION - FOUND McNABB'S 1918 C1/4 & CS1/16 OF SEC 18 & EXTENDED LINE S FROM C1/4 THRU CS1/16 & SET 1/4 COR ON THIS LINE A PROPORTIONATE DISTANCE S. OF CS1/16 ACCEPTED THIS POSITION AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER
- C-1 [NW COR SEC 5] FOUND MONUMENT AS SET BY MYSELF IN 1977 & DESCRIBED AT L.C.R.'S. IN LIBER 2 PAGE 147 ACCEPTED AS A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-1 REPLACED EXISTING MON W/A 5/8" X 18" REBAR W/A ALUMN CAP & RAISED TO RD SURFACE W/A MONUMENT BOX.
- | | | |
|------------|------------|----------------------|
| POWER POLE | POWER POLE | C.L. COUNTY ROAD 525 |
| S85°W | S82°E | WEST |
| 38.00' | 23.83' | 5.5' |
- B-7 SET BERNTSEN AINB30 ALUMN MONUMENT W/A 3-1/4" CAP STAMPED TO ID THE COR POSITION
- | | | |
|------------|----------------|---------------------------|
| POWER POLE | COR FENCE POST | SURVEY MONUMENT SIGN POST |
| N37°W | S79°W | S45°W |
| 46.03' | 24.36' | 1.40' (TO FACE) |

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 11/15/93

Surveyor's Michigan License No. 16926

LIBER 7 PAGE 341