

**SURVEY &
REMONUMENTATION**

DEC 07 1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On November 30, 1993

Chris Schmelwig
Acting Chairman

DELTA COUNTY

LIBER 7 PAGE 340

93 DEC -2 AM 9:00

Walter C. Thoren
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

DELTA (County)	Located In:	Corner Code #/
1. Public Land Survey	T 39 N R 23 W	F-5 & J-13
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
F-5 [1/4 COR COMMON TO SEC'S 9/16] J-13 [S1/4 COR SEC 35]

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- F-5 [1/4 COR COMMON TO SEC'S 9/16] WOOD POST - A. MERRYWEATHER - 1846 (HEMLOCK 6"-N9°E-13 LINKS) (MAPLE 10"-S26°W-8 LINKS)
G. CARLSON - 1989 - L.C.R.'S. IN LIBER 6 PAGE 307
- J-13 [S1/4 COR SEC 35] WOOD POST - JOHN BURT - 1844 (CEDAR 10"-N15°E-22 LINKS) (W.BIRCH 9"-N32°W-17 LINKS)
D.A. BROTHERTON - 1912 - STAKE IN PLACE 42' WEST OF OLD FENCE
M.S. McNABB - 1914 - STAKE IN PLACE - BT'S NOTED (POST 12' HIGH-N85°W-18.5') (W.PINE 3'-S57°E-54.3')
M.S. McNABB - 1919 - IRON STAKE IN PLACE - NO WIT'S NOTED
M.DAVIS - 1977 - FOUND IRON STAKE IN PLACE AS PER L.C.R.'S. IN LIBER 2 PAGE 264

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-5 [1/4 COR COMMON TO SEC'S 9/16] FOUND MONUMENT SET AT MIDPOINT BETWEEN SEC COR'S BY G. CARLSON AS PER L.C.R.'S. IN LIBER 6 PAGE 30
- J-13 [S1/4 COR SEC 35] FOUND IRON PIN AS PER L.C.R.'S. IN LIBER 2 ON PAGE 264
ACCEPTED CORNER MONUMENT AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-5 REPLACED EXISTING MONUMENT W/A 5/8" X 18" REBAR W/A ALUMN CAP STAMPED TO ID THE CORNER POSITION & PLACED 4" BELOW THE ROAD SURFACE
- | | | | |
|------------|-----------|----------|---------------------------|
| POWER POLE | MAPLE 12" | MAPLE 8" | SURVEY MONUMENT SIGN POST |
| N31°W | N24°E | S60°E | S39°W |
| 65.00' | 61.74' | 87.60' | 13.24' (TO FACE) |
- J-13 SET, OVER EXISTING MONUMENT, A 5/8" X 18" REBAR W/A ALUMN CAP STAMPED TO ID COR POSITION & RAISED TO RD SURFACE W/A MON BOX
- | | | | |
|---------------------|------------|---------------------------|--|
| GALV COR FENCE POST | W.PINE 10" | SURVEY MONUMENT SIGN POST | 4TH GALV FENCE POST SOUTH OF CORNER POST |
| N88°W | N74°E | S85°E | S39°E |
| 50.45' (TO FACE) | 37.62' | 15.77' (TO FACE) | 64.50' (TO FACE) |

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 11/15/93
Surveyor's Michigan License No. 16926