

SURVEY & REMONUMENTATION COMMISSION

DEC 07 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On October 21, 1993

Abel Behmeling
Acting Chairman

For corners in

DELTA
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>39 N</u> R <u>23 W</u>	<u>E-7 & F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

DELTA COUNTY

LIBER 7 PAGE 325

93 DEC -2 AM 9:00

Walter A. Thoren
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
NW COR SEC 21 & 1/4 COR COMMON SEC'S 16/21

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, H.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-7 [NW COR SEC 21] A. MERRYWEATHER - 1846 - WOOD POST - CEDAR 12°-S49°E-34 LINKS - HEMLOCK 12°-N60°W-27 LINKS
M.S. McNABB - 1934 - ROAD SURVEY FOR WELLS TWP - IDENTIFIED CORNER POSITION FROM BOTH "GLO" BT'S AND SET IRON BOLT

F-7 [1/4 COR COMMON TO SEC'S 16/21] A. MERRYWEATHER - 1846 - WOOD POST - FIR 4°-S40°W-3 LINKS - FIR 3°-N88°E-10 LINKS
M.S. McNABB - 1934 - ROAD SURVEY FOR WELLS TWP. FOUND WOOD STAKE IN PLACE-SET I.P. & NEW STAKE-W.PINE 9°-S45°E-47' MAPLE 7'-N85°E-36.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 [NW COR SEC 21] FOUND THIS DATE McNABB'S IRON BOLT AS DESCRIBED IN LIBER 1 OF L.C.R.'S. ON PAGE 48 AND ACCEPTED THIS MONUMENT AS A CAREFUL & FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION.

F-7 [1/4 COR COMMON TO SEC'S 16/21] FOUND THIS DATE McNABB'S IRON PIPE & SCRIBED WOOD POST AND ACCEPTED THIS MONUMENT AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 REPLACED EXISTING MONUMENT WITH A 4" X 4" X 36" CONCRETE MONUMENT W/A BRASS CAP STAMPED TO ID THE COR POSITION
CEDAR 9" W. BIRCH 10" CEDAR 10" POWER POLE ALUMN SIGN POST
N47°W N43°E S46°E S47°W N15°W
65.50' 42.08' 102.50' 48.18' (TO FACE)

F-7 REPLACED EXISTING MONUMENT WITH A 4" X 4" X 36" CONCRETE MONUMENT W/A BRASS CAP STAMPED TO ID THE COR POSITION
CEDAR 5" MAPLE 7" HEMLOCK 12" POWER POLE ALUMN SIGN POST
N72°W N68°E S28°E S43°W EAST
97.50' 22.03' 39.82' 61.20' (TO FACE) 2.87' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 10/10/93
Surveyor's Michigan License No. 16926