

SURVEY & REMONUMENTATION

DEC 07 1993

COMMISSION

For corners in DELTA
(County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On November 30 1993

Therese Schmeling
Acting Chairman

DELTA COUNTY

LIBER 1 PAGE 337

93 DEC -2 AM 9:00

Walker A. Hosen
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| | Located In: | Corner Code --# |
|------------------------------------|-----------------------------|----------------------|
| 1. Public Land Survey | T <u>39 N</u> R <u>23 W</u> | <u>G-2 & G-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims G-2 [1/4 COR COMMON TO SEC'S 4/3] G-5 [NW COR SEC 15]

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
G-2 [1/4 COR COMMON TO SEC'S 4/3] WOOD POST - A. MERRYWEATHER - 1846 (CEDAR 12"-N10°E-7 LINKS) (CEDAR 10"-SOUTH-9 LINKS)
M.S. McNABB - 1925 - IRON BOLT IN PLACE - FENCE POSTS -WEST - 20' & EAST - 21'
M. DAVIS - 1974 - MONUMENT FOUND IN PLACE - L.C.R'S. IN LIBER 1 PAGE 417

G-5 [NW COR SEC 15] WOOD POST - A. MERRYWEATHER - 1846 (SPRUCE 10"-N53°W-21 LINKS) (BALSAM 6"-S8°E-12 LINKS)
M.S. McNABB - 1938 - IRON STAKE IN ROAD - COR FENCE POST - SOUTH 24'
G. CARLSON - 1989 - MONUMENT FOUND IN PLACE - L.C.R'S. IN LIBER 6 PAGE 307

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-2 [1/4 COR COMMON TO SEC'S 4/3] FOUND MONUMENT AS DESCRIBED IN L.C.R'S. IN LIBER 1 ON PAGE 417 IN PLACE & 20" BELOW ROAD SURFACE ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER
G-5 [NW COR SEC 15] CORNER MONUMENT DESCRIBED IN L.C.R'S. IN LIBER 6 PAGE 307 HAS BEEN DESTROYED BY RECENT ROAD CONSTRUCTION - RESET
RETRACEMENT OF SURVEYS OF RECORD
ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-2 RAISED CORNER POSITION TO 4" BELOW ROAD SURFACE W/A 5/8" X 18" REBAR W/A ALUMN CAP STAMPED TO ID THE COR POSITION
CEDAR 8" SPRUCE 12" SURVEY MONUMENT SIGN POST
S46°W S83°E WEST
64.25' 58.30' 20.25' (TO FACE)
G-5 SET, INSIDE MON BOX, A 5/8" X 18" REBAR W/A ALUMN CAP STAMPED TO ID THE COR POSITION
CEDAR 8" CEDAR 6" SURVEY MONUMENT SIGN POST
S70°W S35°E N35°E NOTE: LARGE VARIATION OF THE NEEDLE IN THIS AREA
64.90' 94.70' 19.75' BELIEVED TO BE DUE TO ELECTRICAL TRANSMISSION LINE



NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE
Signed by M.P. Davis Date 11/15/93

Surveyor's Michigan License No. 16926

LIBER 7 PAGE 337