

**SURVEY & REMONUMENTATION**

DEC 07 1993

COMMISSION

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On November 30, 1993  
*John R. Schmeiding*  
Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

DELTA COUNTY

For corners in  
DELTA  
(County)

Located In: Corner Code ##

- |                                    |                         |         |
|------------------------------------|-------------------------|---------|
| 1. Public Land Survey              | T 39 N R 23 W           | 1-7 H-7 |
|                                    | T _____ R _____         | _____   |
|                                    | T _____ R _____         | _____   |
|                                    | T _____ R _____         | _____   |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____   |
|                                    | S _____ T _____ R _____ | _____   |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____   |
|                                    | S _____ T _____ R _____ | _____   |

LIBER 7 PAGE 330

93 DEC -2 AM 9:00

*William C. Thoman*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims I-7 [NW COR SEC 23] H-7 [1/4 COR COMMON TO SEC'S 15/22]

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 I-7 [NW COR SEC 23] WOOD POST-A.MERRYWEATHER-1846 (HEMLOCK 10'-N3°W-5 LINKS) (BIRCH 14'-S50°E-8 LINKS)  
 M.S. McNABB-1938-CEDAR STAKE IN PLACE (W.PINE 9'-S10°E-55.5') (W.PINE 9'-N45°W-45')  
 M. DAVIS-1970-SET 1-1/4" I.P. PER L.C.R.'S. IN LIBER 4 PAGE 186
- H-7 [1/4 COR COMMON TO SEC'S 15/22] WOOD POST-A.MERRYWEATHER-1846 (CEDAR 12'-N23°E-8 LINKS) (BIRCH 15'-S30°W-8 LINKS)  
 M. DAVIS-1975-SET 3/4" X 18" I.P. W/A SURVEY CAP PER L.C.R.'S IN LIBER 2 PAGE 132

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 I-7 [NW COR SEC 23] FOUND MONUMENT AS DESCRIBED IN L.C.R.'S. IN LIBER 4 PAGE 186
- H-7 [1/4 COR COMMON TO SEC'S 15/22] FOUND MONUMENT AS DESCRIBED IN L.C.R.'S. IN LIBER 2 PAGE 132



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 I-7 SET, OVER EXISTING MONUMENT, A BERNTSEN A1NB30 ALUMINUM MONUMENT W/A 3-1/4" CAP STAMPED TO ID THE COR POSITION  
 SURVEY MON SIGN POST NW COR CONC TRAP HOUSE  
 NORTH 2.75' TO FACE S4°E - 207.70'  
 COR POSITION IS IN MIDDLE OF GREAT LAKES SPORTS CLUB TRAP RANGE NO OTHER WIT'S NEAR
- H-7 SET, OVER EXISTING MONUMENT, A BERNTSEN A1NB30 ALUMINUM MONUMENT W/A 3-1/4" CAP STAMPED TO ID THE CORN POSITION  
 TWIN MAPLES 5" MAPLE 6" MAPLE 7" MAPLE 8" SURVEY MON SIGN POST  
 N26°W N65°E S28°E S54°W NORTH  
 26.12' 26.62' 26.66' 29.70' 2.82' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCE ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 10/30/93  
 Surveyor's Michigan License No. 16926

LIBER 7 PAGE 330