

**SURVEY &
REMONUMENTATION**

DFC 07 1993

COMMISSIONERS

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On November 30 1993
Robert Schmeling
Chairman

For corners in
DELTA
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------|---|------|-----------|
| 1. Public Land Survey | T | 39 N | R | 23 W | I-3 & I-5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

DELTA COUNTY

LIBER 7 PAGE 327

93 DEC -2 AM 9:00

Walter A. Elmer
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
I-3 [NW COR SEC 11] I-5 [NW COR SEC 14]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
I-3 [NW COR SEC 11] WOOD POST - A. MERRYWEATHER - 1846 (HEMLOCK 12"-N40°E-8 LINKS) (FORKED HEMLOCK 12"-S60°W-24 LINKS)
M.S. McNABE - 1921 - IRON STAKE IN PLACE (COR FENCE POST-S45°W-32.5') (BT STAKE-N45°W-32.5')
M.DAVIS - 1970 - FOUND IRON STAKE IN PLACE - L.C.R.'S. IN LIBER 4 PAGE 183

I-5 [NW COR SEC 14] WOOD POST - A. MERRYWEATHER - 1846 (BEECH 10"-N68°W-48 LINKS) (HEMLOCK 8"-S55°E-14 LINKS)
M.S. McNABB - 1915 - IRON IN PLACE & BT STAKES NORTH & SOUTH 33'
M.S. McNABB - 1938 - " " " (COR FENCE POST SOUTH 24')
M.DAVIS - 1972 - FOUND I.P. IN PLACE - L.C.R.'S. IN LIBER 1 PAGE 49

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I-3 [NW COR SEC 11] FOUND IRON PIN AS DESCRIBED IN L.C.R.'S. IN LIBER 4 PAGE 183
ACCEPTED AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

I-5 [NW COR SEC 14] FOUND I.P. AS DESCRIBED IN L.C.R.'S. IN LIBER 1 PAGE 49
ACCEPTED AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-3 SET, OVER EXISTING MONUMENT, A 5/8" X 18" REBAR W/A ALUMN CAP STAMPED TO ID COR POSITION & RAISED TO RD SURFACE W/A MON BOX

CONC PLAT MON	POWER POLE	SURVEY MONUMENT SIGN POST
N40°W	N47°E	S47°W
46.10'	43.80'	47.30' (TO FACE)

I-5 SET, OVER EXISTING MONUMENT, A 5/8" X 18" REBAR W/A ALUMN CAP STAMPED TO ID COR POSITION & RAISED TO RD SURFACE W/A MON BOX

NE COR OF HOUSE	SPRUCE 13"	SURVEY MONUMENT SIGN POST
S33°W	S49°E	SOUTH
57.75'	93.10'	18.97' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCE ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 10/30/93
Surveyor's Michigan License No. 16926