

**SURVEY &
REMONUMENTATION**

DEC 07 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On October 21, 1993

Arthur E. Schmelking
Acting Chairman

DELTA COUNTY

For corners in

DELTA
(County)

Located In:

Corner Code ##

- | | | | | |
|---------------------------------------|--------|--------|------|-------------|
| 1. Public Land Survey | T 39 N | R 23 W | H-11 | <u>1-11</u> |
| | T | R | | |
| | T | R | | |
| | T | R | | |
| 2. Property Controlling
in Section | S | T | R | |
| | S | T | R | |
| 3. Miscellaneous
Property in Sec. | S | T | R | |
| | S | T | R | |

LIBER 7 PAGE 314

98 DEC -2 AM 9:00

Walter C. Thomas
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
1/4 COR COMMON TO SEC'S 27/34 & NW COR SEC 35

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-11 [1/4 COR COMMON TO SEC'S 27/34] A. MERRYWEATHER - 1846 - WOOD POST - CEDAR 7"-N82°E-5 LINKS - CEDAR 6"-S79°W-8 LINKS
M. DAVIS - 1972 - 1-1/2" IRON PIPE SHOWN TO ME BY CHARLES DeGRAND -LONG TIME PROPERTY OWNER, WHO STATED CORNER POSITION WAS SET BY J.E. GINGRASS, COUNTY SURVEYOR, MR. DeGRAND COULD NOT RECALL THE DATE THE CORNER WAS ESTABLISHED.

I-11 [NW COR OF SEC 35] A. MERRYWEATHER - 1846 - WOOD POST - CEDAR 8"-N60°E-3 LINKS - Y.PINE 12"-S70°W-21 LINKS
M.S. McNABB - 1932 - IDENTIFIED COR POSITION FROM ORIGINAL "GLO" NE BT -NOTED NEW BT'S CEDAR 7"-N2°W-10.2 - CEDAR 6"-S75°E-7.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11 FOUND 1-1/2" I.P. AS DESCRIBED IN LIBER 1 OF L.C.R.'s, ON PAGE 295 - CORNER FALLS IN WEST WHEEL PATH OF N-S WOODS ROAD
ACCEPTED EXISTING MONUMENT AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE ORIGINAL CORNER.

I-11 I.P. MONUMENT AS DESCRIBED IN LIBER 2 OF L.C.R.'s, ON PAGE 375 HAS BEEN REMOVED - RESET CORNER POSITION FROM EXISTING BT'S AS RECORDED THEREIN. ACCEPTED AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 SET BERNTSEN A1NB30 ALUMINUM MONUMENT W/A 3-14" CAP STAMPED TO ID THE CORNER POSITION OVER THE EXISTING I.P.
MAPLE 6" MAPLE 5" SURVEY MON. SIGN POST
N23°W S68°W EAST
32.95' 18.75' 11.60' (TO FACE)

I-11 SET BERNTSEN A1NB30 ALUMINUM MONUMENT W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION
CEDAR 14" CEDAR 11" CEDAR 11" ASH 14" SURVEY MON. SIGN POST
N3°E N62°E S52°E S57°W EAST
10.11' 23.40' 27.96' 14.61' 2.98' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis

Date 10/10/93

Surveyor's Michigan License No. 16926