

# SURVEY & REMONUMENTATION

DEC 07 1993

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On November 30, 1993

*Charles E. Humling*  
Acting Chairman

DELTA COUNTY

For corners in

DELTA

(County)

Located In:

Corner Code #

1. Public Land Survey	T 39 N R 23 W	K-4 & K-5
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

LIBER 7 PAGE 328

93 DEC -2 AM 9:00

*Walter C. Thoren*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_  
K-4 [1/4 COR COMMON TO SEC'S 11/12] K-5 [NW COR SEC 13]

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- K-4 [1/4 COR COMMON TO SEC'S 11/12] WOOD POST - A. MERRYWEATHER - 1846 (BIRCH 10"-S50°E-6 LINKS) (HEMLOCK 12"-N40°W-10 LINKS)
  - D.A. BROTHERTON - 1907 - ID FROM ORIGINALS - NET BEECH 8"-N60°E-38.5
  - M.S. McNABB - 1926 - WOOD STAKE IN PLACE - COR FENCE POSTS - WEST 30.7' & EAST 16'
  - M. DAVIS - 1970 - FOUND IRON PIN IN PLACE - L.C.R.'S IN LIBER 4 ON PAGE 185
  - K-5 [NW COR SEC 13] WOOD POST - A. MERRYWEATHER - 1846 (BIRCH 7"-S53°W - 24 LINKS) (MAPLE 8"-N73°E-8 LINKS)
  - M.S. McNABB - 1915 - ID FROM BOTH ORIGINALS - SET I.P. 5' LONG FOR COR - NO WIT'S NOTED
  - T.P. O'BRIEN - 1978 - FOUND 1-1/4" I.P. - L.C.R.'S, LIBER 2 PAGE 208

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- K-4 [1/4 COR COMMON TO SEC'S 11/12] FOUND IRON PIN AS DESCRIBED IN L.C.R.'S LIBER 4 PAGE 185 - 15' BELOW EXISTING ROAD SURFACE ACCEPTED CORNER MONUMENT AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER
  - K-5 [NW COR SEC 13] FOUND 1-1/4" IRON PIPE AS DESCRIBED IN L.C.R.'S, LIBER 2 PAGE 208 - ACCEPTED CORNER MONUMENT AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-4 RAISED TO COUNTY ROAD SURFACE W/A MONUMENT BOX & A 5/8" X 18" REBAR W/A ALUMN CAP STAMPED TO ID THE COR POSITION

POWER POLE	BEECH 15'	ANCHOR POLE	SURVEY MONUMENT SIGN POST
N35°W	N64°E	S40°E	S60°W
40.25'	42.35'	35.75'	34.90' (TO FACE)

  - K-5 SET, OVER EXISTING MONUMENT, A BERNTSEN AINB30 ALUMN MON W/A CAP STAMPED TO ID THE COR POSITION

SURVEY MONUMENT SIGN POST

S45°E                      NOTE: ALL BT'S SHOWN AT L.C.R.'S, LIBER 2 PAGE 208 ARE STILL GREEN & VIALBLE

1.21' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCE ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 10/30/93  
Surveyor's Michigan License No. 16926