

SURVEY & REMONUMENTATION

DEC 07 1993

COMMISSION

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On November 30 1993

Charles Shmeling
Acting Chairman

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DELTA COUNTY

For corners in

DELTA

(County)

Located In:

Corner Code #

LIBER 7 PAGE 328

93 DEC -2 AM 9:00

Walter A. Johnson
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- | | | |
|------------------------------------|-----------------------------|----------------------|
| 1. Public Land Survey | T <u>39 N</u> R <u>23 W</u> | <u>K-4 & K-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
K-4 [1/4 COR COMMON TO SEC'S 11/12] K-5 [NW COR SEC 13]

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
 K-4 [1/4 COR COMMON TO SEC'S 11/12] WOOD POST - A. MERRYWEATHER - 1846 (BIRCH 10"-S50°E-6 LINKS) (HEMLOCK 12"-N40°W-10 LINKS)
 D.A. BROTHERTON - 1907 - ID FROM ORIGINALS - NBT BEECH 8"-N60°E-38.5
 M.S. McNABB - 1926 - WOOD STAKE IN PLACE - COR FENCE POSTS - WEST 30.7' & EAST 16'
 M. DAVIS - 1970 - FOUND IRON PIN IN PLACE - L.C.R'S IN LIBER 4 ON PAGE 185

- K-5 [NW COR SEC 13] WOOD POST - A. MERRYWEATHER - 1846 (BIRCH 7"-S50°W - 24 LINKS) (MAPLE 8"-N73°E-8 LINKS)
 M.S. McNABB - 1915 - ID FROM BOTH ORIGINALS - SET I.P. 5' LONG FOR COR - NO WIT'S NOTED
 T.P. O'BRIEN - 1978 - FOUND 1-1/4" I.P. - L.C.R'S, LIBER 2 PAGE 208

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 K-4 [1/4 COR COMMON TO SEC'S 11/12] FOUND IRON PIN AS DESCRIBED IN L.C.R'S LIBER 4 PAGE 185 - 15" BELOW EXISTING ROAD SURFACE
 ACCEPTED CORNER MONUMENT AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER
 K-5 [NW COR SEC 13] FOUND 1-1/4" IRON PIPE AS DESCRIBED IN L.C.R'S, LIBER 2 PAGE 208 - ACCEPTED CORNER MONUMENT AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-4 RAISED TO COUNTY ROAD SURFACE W/A MONUMENT BOX & A 5/8" X 18" REBAR W/A ALUMN CAP STAMPED TO ID THE COR POSITION
- | | | | |
|------------|-----------|-------------|---------------------------|
| POWER POLE | BEECH 15" | ANCHOR POLE | SURVEY MONUMENT SIGN POST |
| N35°W | N64°E | S40°E | S60°W |
| 40.25' | 42.35' | 35.75' | 34.90' (TO FACE) |

- K-5 SET, OVER EXISTING MONUMENT, A BERNTSEN AINB30 ALUMN MON W/A CAP STAMPED TO ID THE COR POSITION
 SURVEY MONUMENT SIGN POST
 S45°E
 1.21' (TO FACE)
 NOTE: ALL BT'S SHOWN AT L.C.R'S, LIBER 2 PAGE 208 ARE STILL GREEN & VIALBLE

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCE ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 10/30/93
 Surveyor's Michigan License No. 16926