

**SURVEY &  
REMONUMENTATION**

DEC 07 1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Approved by Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On October 21, 1993  
*Robert E. Schmeling*  
Acting Chairman

DELTA COUNTY

LIBER 7 PAGE 317

93 DEC -2 AM 9:00

*Walter A. Thoren*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in  
DELTA  
(County)

Located In: Corner Code: #

- |                                    |                             |                       |
|------------------------------------|-----------------------------|-----------------------|
| 1. Public Land Survey              | T <u>39</u> N R <u>23</u> W | <u>C-11 &amp; L-7</u> |
|                                    | T _____ R _____             | _____                 |
|                                    | T _____ R _____             | _____                 |
|                                    | T _____ R _____             | _____                 |
| 2. Property Controlling in Section | S _____ T _____ R _____     | _____                 |
|                                    | S _____ T _____ R _____     | _____                 |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____     | _____                 |
|                                    | S _____ T _____ R _____     | _____                 |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
NW COR SEC 32 & 1/4 COR COMMON TO SEC'S 13/24

I, M.P. DAVIS, in a field survey on MAY, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

C-11 [NW COR SEC 32] A. MERRYWEATHER - 1846 - WOOD POST - BALSAM 6" WEST 8 LINKS - TANERAC 8"-S80°E-4 LINKS  
M.S. MCNABB - 1918 - FOUND WOOD STAKE IN PLACE & OCCUPATION LINES - BT STAKE S45°E-33'

L-7 [1/4 COR COMMON TO SEC'S 13/24] A. MERRYWEATHER - 1846 - WOOD POST - BIRCH 10" N10°E 8 LINKS-BIRCH 5"-S30°W-4 LINKS  
M.S. MCNABB - 1915 - IRON FOUND IN PLACE-T.P. S8°15'E-54.6' - SE COR BARN N44°40'E-81.5

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 [NW COR SEC 32] FOUND IRON BOLT & REMAINS OF WOOD POST IN PLACE-ID COR POSITION FROM M.D.O.T. SURVEY RECORDS FOR HWY U.S. 2 - BELIEVE THIS MONUMENT REPRESENTS MCNABB'S 1918 MONUMENT AS HE FOUND IT IN PLACE - ACCEPTED THIS EXISTING MONUMENT AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

L-7 [1/4 COR COMMON TO SEC'S 13/24] ID CORNER POSITION BY EXISTING PLAT MONUMENT, FROM THE PLAT OF ESCANABA INDUSTRIAL PARK NO. 1 AS REC'D IN LIBER "C" OF PLATS ON PAGES 60-61. ACCEPTED EXISTING MONUMENT AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 REPLACED EXISTING IRON BOLT WITH A BERNTSEN A1NE30 ALUMINUM MONUMENT W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION

|          |          |          |          |                           |
|----------|----------|----------|----------|---------------------------|
| CEDAR 6" | MAPLE 7" | MAPLE 9" | CEDAR 5" | SURVEY MONUMENT SIGN POST |
| N32°W    | N37°E    | S53°E    | S60°W    | EAST                      |
| 19.37'   | 34.90'   | 60.70'   | 27.30'   | 1.97' (TO FACE)           |

L-7 REPLACED PLAT MONUMENT WITH A 4" X 4" X 36" CONCRETE MONUMENT W/A BRASS CAP STAMPED TO ID THE CORNER POSITION

|                 |                  |                           |
|-----------------|------------------|---------------------------|
| NW COR OF BLDG. | POWER POLE       | SURVEY MONUMENT SIGN POST |
| S54°W           | N71°E            | S45°E                     |
| 31.35'          | 27.22' (TO FACE) | 2.18' (TO FACE)           |

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCE ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 10/10/93

Surveyor's Michigan License No. 16926