

**SURVEY &
REMONUMENTATION**

DEC 07 1993

COMMISSION

For corners in
DELTA
(County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 Ord. Number 30, 1993
Robert Schmelting
Acting Chairman

DELTA COUNTY

LIBER 7 PAGE 335

93 DEC -2 AM 9:00

Walter A. Thoman
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	Located In:	Corner Code #
1. Public Land Survey	T <u>39 N</u> R <u>23 W</u>	<u>D-11 & L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims D-11 [1/4 COR COMMON TO SEC'S 29/32] L-11 [1/4 COR COMMON TO SEC'S 25/36]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-11 [1/4 COR COMMON TO SEC'S 29/32] WOOD POST - A. MERRYWEATHER - 1846 (BIRCH 9"-S17"E-27 LINKS) (HEMLOCK 12"-N18"E-8 LINKS)
M.S. McNABB - 1914 - STAKE & IRON IN PLACE - NBT STAKES NE & SW 33' - C.L. RR TRACKS SOUTH 150.5' - C.L. N-S COUNTY ROAD EAST 5'
M. DAVIS - 1971 - CORNER DESTROYED IN ROAD IMPROVEMENTS - RESET FROM ABOVE McNABB REFERENCES
B. TAAVOLA - 1982 - L.C.R.'S. IN LIBER 5 PAGE 100

L-11 [1/4 COR COMMON TO SEC'S 25/36] WOOD POST - A. MERRYWEATHER - 1846 (TAMERAC 4"-EAST-2 LINKS) (TAMERAC 7" -S68"W-16 LINKS)
D.A. BROTHERTON - 1909 - STAKE IN PLACE - NO WIT'S NOTED
M.S. McNABB - 1919 - CONC MONUMENT IN PLACE FROM CITY OF ESCANABA RECORDS - NO WITS NOTED
M.S. McNABB - 1936 - CONC MONUMENT IN PLACE - NO WIT'S NOTED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 [1/4 COR COMMON TO SEC'S 25/36] FOUND I.P. & MON BOX AS DESCRIBED IN L.C.R.'S. IN LIBER 5 PAGE 100 BENEATH NEW ROAD SURFACE
ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

L-11 [1/4 COR COMMON TO SEC'S 25/36] FOUND 3/4" IRON PIN/CONC MONUMENT BURIED BENEATH NEW ROAD SURFACE - REFERENCE L.C.R.'S. LIBER 2 PAGE 266
ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11 SET, OVER EXISTING I.P., A 5/8" X 18" REBAR W/A ALUMN CAP STAMPED TO ID THE COR POSITION & RAISED EXISTING MON BOX TO RD SURFACE:
NE COR OF HOUSE SURVEY MONUMENT SIGN POST RED PINE 10" SE COR OF GARAGE
N34°W EAST S48°E S69°W
89.65' 25.66' (TO FACE) 68.37' 53.84'

L-11 SET, OVER EXISTING MON, A 5/8" X 18" REBAR W/A ALUMN CAP STAMPED TO ID THE COR POSITION & RAISED TO RD SURFACE W/A MON BOX
NW COR OF HOUSE POWER POLE POWER POLE FIRE HYD
S54°E S25°W N6°W N35°E
77.86' 145.87' 71.42' 72.16'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 11/15/93
Surveyor's Michigan License No. 16926