



Approved by Delta County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On Sept 23, 1993  
*Robert Schmelking*  
 Acting Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
DELTA  
 (County)

Located In: \_\_\_\_\_ Corner Code #  
 T 39 N R 24 W C-8 & C-9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Liber 7 Pg. 307*

Register of Deeds Stamp & File Number

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims  
1/4 CORNER COMMON TO SEC'S 19/20 AND SW CORNER OF SEC 20

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- C-8 [1/4 CORNER COMMON TO SEC'S 19/20] GEORGE ADAIR-1852-(BEECH 15'-N15°E-12 LINKS) (HEMLOCK 18"-S20°W-18 LINKS) D.A. BROTHERTON-1912-IDENTIFIED FROM REMAINS OF WOOD STAKE FOUND IN PLACE-RESET 3/4" X 16" IRON STAKE (FENCE POST-SE-74.9") M.S. McNABB-1918-FOUND IRON STAKE IN PLACE (POST-NORTH 23.8') (FENCE POST-S30°E-76')
  - C-9 [SW COR SEC 20] WOOD POST-GEORGE ADAIR-1852-(CEDAR N46°W-25 LINKS) (CHERRY 10"-S65°E-20 LINKS) M.S. McNABB-1918-IDENTIFIED CORNER POSITION BY IRON STAKE FOUND IN ROADBED (ELM 20"-N18°W-53.5') [NO MENTION IN McNABB RECORDS OF ORIGINAL EVIDENCE FOUND]
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- C-8 [1/4 CORNER COMMON TO SEC'S 19/20] IDENTIFIED CORNER POSITION FROM IRON STAKE MENTIONED IN McNABB'S NOTES (NO EVIDENCE OF HIS BT ACCEPTED THIS MONUMENT AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
  - C-9 [SW CORNER SEC 20] NO EVIDENCE OF IRON STAKE MENTIONED IN McNABB'S NOTES OR HIS ELM BT - FOUND 1/4 CORNER COMMON TO SEC'S 19/30 & E1/16 BETWEEN SEC'S 19/30-EXTENDED SURVEY LINE EAST FROM 1/4 CORNER THRU E1/16 AND ESTABLISHED SEC CORNER ON THIS LINE AT PROPORTIONATE DISTANCE EAST OF 1/16 CORNER. ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE ORIGINAL CORNER.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- C-8 SET BERNTSEN A1NB30 ALUMINUM MONUMENT W/A 3-1/4" CAP STAMPED TO IDENTIFY THE CORNER POSITION.  
 POWER POLE ANCHOR POLE NE CORNER OF HOUSE  
 N52°E N71°W S34°W  
 48.95' 94.65' 114.20'
  - C-9 SET, INSIDE OF A MONUMENT BOX, A 5/8" X 18" REBAR WITH A 3-1/4" ALUMINUM CAP STAMPED TO IDENTIFY THE CORNER POSITION.  
 POWER POLE ANCHOR POLE ASH 10" ALUMINUM SIGN POST  
 S50°W S29°E N33°E N45°W  
 47.52' 46.40' 79.90' 38.70'(TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE.  
 Signed by M.P. Davis Date 9/22/93  
 Surveyor's Michigan License No. 16926