

**SURVEY &
REMONUMENTATION**

SEP 13 1994

COMMISSION

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On July 13, 1994

R. B. Schulz
Acting Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
DELTA

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 39 N R 24 W
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

E-10 & E-11

Recorded Aug 12 1994
at 9:00 clock AM in Liber 8 Page 46
John C. Brown Reg. of Deeds.
Delta County, Michigan

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims E-10 [W1/4 COR S.28] E-11 [NW COR S.33]

I, M.P. DAVIS, in a field survey on MAY/JUNE, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-10 [W1/4 COR S.28] GEORGE ADAIR, D.S. - 1852 - WOOD POST (SUGAR 14"-N44°W-20 LINKS) (IRONWOOD 08"-S20°E-40 LINKS)
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION

E-11 [NW COR S.33] GEORGE ADAIR, D.S. - 1852 - WOOD POST (Y. BIRCH 11"-N63°W-22 LINKS) (CEDAR 18"-S52°E-15 LINKS)
M.S. McNABB-(NO DATE)-IDENTIFIED FROM ORIGINAL BIRCH BT NW (CEDAR STUMP 16"-N22°W-12') (CEDAR STUMP 14'-S10°W-18')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-10 [W1/4 COR S.28] FOUND IRON PIN IN PLACE AS INDICATED BY ANCIENT FARM FENCE WEST & COUNTY ROAD IMPROVEMENTS N & S. NO EVIDENCE AVAILABLE AS TO THE ORIGIN OF THE EXISTING MONUMENT. ACCEPTED SAME AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.

E-11 [NW COR S.33] CHAINED WEST FROM 1/4 CORNER COMMON TO SEC'S 28/33 ALONG FARM FENCE LINE A DISTANCE OF 2640' M/L AT WHICH POINT I FOUND THE REMAINS OF A SQ'D CEDAR POST AT THE JCT. OF FENCE LINES N-S & E, FROM WHICH A Y, BIRCH SNAG (12' HIGH) BEARS N63°W-22 LINKS. BLAZE MARKS ARE STILL PLAIN ALTHOUGH THEY ARE BURNT OUT & THE SCRIBING HAS BEEN DESTROYED. BOTH OF McNABB'S CEDAR STUMP BT'S ARE STILL IN PLACE WITH SCRIBING PLAIN. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-10 SET, OVER EXISTING MONUMENT & 6" BELOW RD SURFACE A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.

ELM 24"	POWER POLE	SURVEY MONUMENT SIGN POST	
WEST	S67°E	N45°E	NO OTHER WIT'S AVAILABLE
28.75'	32.11' (TO FACE)	22.15' (TO FACE)	FARM FIELDS IN ALL FOUR QUAD'S

E-11 REPLACED EXISTING POST W/A BERNTSEN AINB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.

CEDAR 7"	CEDAR 5"	CEDAR 5"	ASH 9"	SURVEY MONUMENT SIGN POST
N23°W	N51°E	S77°E	S18°W	S45°E
10.08'	13.15'	14.19'	9.05'	2.15' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 6/30/94
Surveyor's Michigan License No. 16926