

SEP 1 3 1994

COMM

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On June 8, 1994

Robert Schumling
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 39 N R 24 W G-10 & G-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Recorded JUN - 9 1994
at 9:00 o'clock AM in Liber 8 Page 16
William C. Thuman Reg. of Deeds,
Delta County, Michigan
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims G-10 [W1/4 COR S.27] G-11 [NW COR S.34]

I, M. P. DAVIS, in a field survey on MAY, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G-10 [W1/4 COR S.27] GEORGE ADAIR, D.S. - 1852 - WOOD POST (IRONWOOD 08°-N72°E-17 LINKS) (BEECH 06°-S73°W 25 LINKS)
M.S. McNABB - 1919 - IDENTIFIED BY IRON STAKE IN HWY NOTED NEW BT'S (ELM 2°-S2°W-20') (FENCE POST-WEST-17')
- G-11 [NW COR S.34] GEORGE ADAIR, D.S. - 1852 - WOOD POST (SUGAR 15°-N40°W-18 LINKS) (BEECH 10°-S43°E-23 LINKS)
D.A. BROTHERTON - 1910 - IDENTIFIED FROM IRON STAKE IN PLACE, NOTED NEW BT'S (FENCE POSTS-N51°W-35.6', N45°E-24.6' & N30°W-27')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-10 [W1/4 COR S.27] FOUND 28" M/L BELOW COUNTY ROAD SURFACE A 1" SOLID IRON PIN. IDENTIFIED CORNER MONUMENT AS THAT BEING FOUND IN 1919 BY McNABB BY EXISTING OCCUPATION EAST & COUNTY ROAD IMPROVEMENTS N & S AND COMPARISON OF McNABB'S REC'D DISTANCES TO ADJOINING CORNERS N & S. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.
- G-11 [NW COR S.34] FOUND IN PLACE A BUGGY AXEL 12" M/L BELOW COUNTY ROAD SURFACE. NO EVIDENCE OF BROTHERTON'S 1910 BT'S. DISTANCES WEST & SOUTH CHECK WELL WITH THE RECORDS OF BROTHERTON. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-10 SET OVER EXISTING MON & RAISED TO 6" BELOW RD SURFACE W/A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE COR POSITION
POWER POLE MAPLE 27" ELM 9" SURVEY MONUMENT SIGN POST
N20°W S89°E S51°W S51°E
56.89' (TO FACE) 67.38' 22.92' 36.49' (TO FACE)
- G-11 SET, OVER EXISTING MON & INSIDE A MON BOX A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.
RED PINE 8" DRILL HOLE IN LARGE FIELD STONE MAPLE 17" SURVEY MONUMENT SIGN POST
N27°W N20°E S57°W SOUTH
56.67' 39.98' 105.41' 24.30' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG IN THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 6/7/94
Surveyor's Michigan License No. 16926