

FEB 22 1996

COMMISSION

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On 10/26, 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Robert Schmalz Acting Chairman

For corners in DELTA (County) Located In: Corner Code ## 1. Public Land Survey T 38 NR 24 W G-13 & H-1 T 39N R 24W H-13

Recorded Oct 27 1995 at 9:00 o'clock AM in Liber 8 Page 107 Wallace C. Thomas Reg. of Deeds. Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims 6-13 [SW COR S.34] SAME AS G-1 T37N R24W H-1 [N1/4 COR S.3] SAME AS H-18 T39N R24W

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column H and row 1.

I, M.P. DAVIS, in a field survey on MAY, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: G-13 [SW COR S.34] JAMES H. MULLETTE, D.S. - 1847 - WOOD POST - (Y. BIRCH 10°-N63°E-21 LINKS) (Y. BIRCH 08°-N58°W-45 LINKS) GEORGE ADAIR, D.S. - 1852 - WOOD POST - (CEDAR 12°-S05°W-38 LINKS) (CEDAR 16°-S21°E-43 LINKS) from survey of T37N R24W M.S. McNABB-1918-IDENTIFIED BY ORIGINAL CEDAR BT, NOW A 16" STUMP, RESET STAKE & BT STAKES NW & SE 33' F. BRAY-M.D.N.R.-1969-SET 1-1/4" I.P. FROM OCCUPATION & WHERE LAND OWNER RECALLS SEEING A WOOD STAKE IN PLACE (COR POST-SOUTH-29 LINKS) (GUARD RAIL POST-S71°E-44 LINKS) (GUARD RAIL POST-N70°E-46 LINKS) H-1 [N1/4 COR S.3] JAMES H. MULLETTE, D.S. - 1848 - WOOD POST - (TAMARACK 08°-N57°W-40 LINKS) (TAMARACK 06°-S71°W-07 LINKS) NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: G-13 [SW COR S.34] FOUND IN PLACE THE ABOVE MENTIONED MONUMENT AS PLACED BY FRANK BRAY IN 1969, ID CORNER MONUMENT BY REFERENCE TO BOTH GUARD RAIL BT'S AS NOTED IN BRAY'S LCR RECORDED IN LIBER 4 ON PAGE 81. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.



H-1 [N1/4 COR S.3] NO ORIGINAL CORNER EVIDENCE FOUND & NO IDENTIFIABLE INDICATION OF SUBSEQUENT CORNER RESTORATION FOUND. REESTABLISHED CORNER POSITION AT MIDPOINT BETWEEN SECTION CORNERS 1/2 MILE EAST & WEST.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: G-13 SET OVER EXISTING MON A 5/8" X 18" REBAR W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION. ELM 9" END GUARD RAIL POST END GUARD RAIL POST POWER POLE SURVEY MONUMENT SIGN POST N36°W N70°E S71°E S65°W SOUTH 15.30' 31.26' (TO FACE) 34.94' (TO FACE) 72.20' (TO FACE) 17.13' (TO FACE) H-1 SET BERNTSEN AINB30 ALUMN MONUMENT W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION. TAMARACK 6" TAMARACK 6" TAMARACK 5" TAMARACK 5" SURVEY MONUMENT SIGN POST N32°E S72°E S20°E S52°W NORTH 6.91' 31.11' 24.81' 19.71' 1.95' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 10/24/95 Surveyor's Michigan License No. 16926