

# SURVEY & REMONUMENTATION

SEP 13 1994

COMMISSION

Approved by Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On June 8, 1994

*Robert Schueler*  
Acting Chairman

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
DELTA  
(County)

Located in: Corner Code #

- |                                       |                             |             |
|---------------------------------------|-----------------------------|-------------|
| 1. Public Land Survey                 | T <u>39</u> N R <u>24</u> W | K-10 & K-11 |
|                                       | T _____ R _____             | _____       |
|                                       | T _____ R _____             | _____       |
|                                       | T _____ R _____             | _____       |
| 2. Property Controlling in Section    | S _____ T _____ R _____     | _____       |
|                                       | S _____ T _____ R _____     | _____       |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____     | _____       |
|                                       | S _____ T _____ R _____     | _____       |
| 4. Lot No. _____, Recorded Plat _____ |                             |             |
| 5. Private Claims _____               |                             |             |

K-10 [W1/4 COR S.25] K-11 [NW COR S.36]

Recorded JUN -9 1994  
at 9:00 o'clock AM in Liber 8 Page 23  
*Walter C. Thum* Reg. of Deeds.  
Delta County, Michigan  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, M.P. DAVIS, in a field survey on MAY, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**


K-10 [W1/4 COR S.25] GEORGE ADAIR, D.S. - 1852 - WOOD POST (HEMLOCK 07°-N21°W-12 LINKS) (HEMLOCK 07°-S54°E-06 LINKS) D.A. BROTHERTON - 1910 - FOUND STAKE IN HWY & NOTED NEW BT'S (TAM 12°-N24°W-37.3') (TAM 5°-S38°E-31')

K-11 [NW COR S.36] GEORGE ADAIR, D.S. - 1852 - WOOD POST (BEECH 10°-N48°E-51 LINKS) (BEECH 06°-S41°W-43 LINKS) 1878 RECORDS ON C.E. BROTHERTON INDICATE CORNER IN PLACE - NO DESCRIPTION OF EXISTING MONUMENT OR ACCESSORIES GIVEN M.S. McNABB - 1920 - RD ALIGNMENT SURVEY FOR WELLS TWP - STAKE IN PLACE (FENCE POST N5°W-33') (FENCE POST-N30°E-40.1') M.DAVIS-1974-ESTABLISHED COR POSITION BY RETRACEMENT OF McNABB'S 1920 ROAD ALIGNMENT SURVEY-REC'D LCR'S L.2 PAGE 80.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-10 [W1/4 COR S.25] FOUND IN PLACE A 1" IRON BOLT & THE POINTED REMAINS OF A WOOD STAKE. THE "HWY" REFERRED TO IN BROTHERTON'S NOTES IS NOW A LITTLE USED N-S WOODS ROAD, NO EVIDENCE OF BROTHERTON'S WIT'S REMAINS. ACCEPTED EXISTING MONUMENT AS THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

K-11 [NW COR S.36] FOUND IP IN MON BOX A ESTABLISHED IN 1974, ALL WIT'S HAVE BEEN REMOVED. ACCEPTED THIS POSITION AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE OF THE ORIGINAL CORNER.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-10 SET OVER EXISTING MONUMENT A BERNTSEN A1NB30 ALUMN MON WITH THE CAP STAMPED TO ID THE CORNER POSITION.

TAMARACK 13"	TAMARACK 7"	TAMARACK 7"	CEDAR 7"	SURVEY MONUMENT SIGN POST
N2°W	N42°E	S45°E	S76°W	S75°E
70.16'	61.63'	32.91'	20.29'	11.24' (TO FACE)

K-11 REPLACED IP W/A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION

RED PINE 5"	CORNER FENCE POST	SURVEY MONUMENT SIGN POST
S36°W	N29°E	SOUTH
43.00'	28.70'	25.86' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG IN THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 6/7/94

Surveyor's Michigan License No. 16926