

SURVEY & REMONUMENTATION

SEP 13 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On May 19, 1994

Robert Schmeling
Acting Chairman

For corners in
DELTA
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>39</u> N R <u>24</u> W | L-11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded JUN -8 1994
at 9:00 a'clock AM in Liber 8 Page 4
Walter C. Thoma
Reg. of Deeds.
Delta County, Michigan
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims L-11 [N1/4 COR S.36]

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on MAY, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
L-11 [N1/4 COR S.36] GEORGE ADAIR, D.S. - 1852 - WOOD POST (HEMLOCK 08°-N52°E-24 LINKS) (CEDAR 12°-S39°W-50 LINKS)
1878 RECORDS OF C.E. BROTHERTON SHOWS CORNER IN PLACE NO DESCRIPTION OF EXISTING MONUMENT OR ACCESSORIES GIVEN
M.S. McNABB - 1920 - ROAD ALIGNMENT SURVEY - CORNER STAKE IN PLACE - FENCE POST NORTH 31.4' & SOUTH 32.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
L-11 [N1/4 COR S.36] FOUND IN PLACE A 1" IRON PIPE IN A MONUMENT BOX SET BY MYSELF IN 1974 AND REC'D IN LIBER 2 ON PAGE 78 OF LCR'S. CORNER POSITION WAS IDENTIFIED FROM McNABB'S 1920 CORNER FENCE POST BT (DOWN & IN POOR CONDITION, SCRIBE MARKS PLAIN) NORTH-31.4'.
ACCEPTED EXISTING POSITION AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 REPLACED IRON PIPE W/A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.

CORNER FENCE POST	ELM 6"	SPRUCE 9"	CEDAR 7"	SURVEY MONUMENT SIGN POST
N5°W	N53°E	S30°E	S27°W	SOUTH
42.70'	65.00'	58.58'	62.14'	26.06' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG IN THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 5/19/94
Surveyor's Michigan License No. 16926