

REMONUMENTATION

FEB 22 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On October 21, 1993

Philip E. Schmeling  
Delta County Chairman

DELTA COUNTY

LIBER 7 PAGE 318

93 DEC -2 AM 9:00

Wallace C. Thomsen  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in DELTA (County)

Located In: Corner Code #/

1. Public Land Survey T 39 N R 23 W A-5 & A-9  
 T 39 N R 24 W M-5

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims NW COR SEC 18 & NW COR SEC 30 - SAME AS M-5, M-9 T39N R24W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	3	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 A-5 [NW COR SEC 18] J. BURT-1845-WOODPOST - Y. BIRCH 10"-S48°W-17 LINKS - HEMLOCK 22"-N56°W-18 LINKS.  
 D.A. BROTHERTON-1908-ROAD SURVEY FOR FORD RIVER TWP.-ESTABLISHED CORNER POSITION BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN W1/4 OF SEC 18 & NW COR SEC 7. BT STAKE-S78°W-25' BT STAKE-N73°E-27.3'

A-9 [NW COR SEC 30] J. BURT - 1845 - WOOD POST - SUGAR 14"-S23°W-38 LINKS - SUGAR 10"-N70°W-28 LINKS  
 D.A. BROTHERTON - 1910 - IDENTIFIED BY STAKE IN PLACE - ELM 16" N40°W-62.3'  
 M.S. McNABB - 1913 - IDENTIFIED BY STAKE IN PLACE - SET IRON STAKE - ELM 16" N40°W-62.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 A-5 [NW COR SEC 18] FOUND THIS DATE IRON PIPE IN MONUMENT BOX AS DESCRIBED IN LIBER 1 OF L.C.R'S. ON PAGE 317 AND ACCEPTED THIS MONUMENT AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE ORIGINAL CORNER POSITION.

A-9 [NW COR SEC 30] FOUND THIS DATE IRON PIPE IN MONUMENT BOX AS DESCRIBED IN LIBER 7 OF L.C.R'S. ON PAGE 192 AND ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE ORIGINAL CORNER POSITION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 A-5 REPLACED EXISTING MONUMENT WITH A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION  
 CEDAR 10" CEDAR 12" CHISELED X ON CONC CROSS PIPE SURVEY MON. SIGN POST  
 S61°W S46°E N38°W EAST  
 67.02' 48.30' 36.50' 33.0' (TO FACE)

A-9 REPLACED EXISTING MONUMENT WITH A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORN POSITION  
 POWER POLE SURVEY MON. SIGN POST ROAD SIGN POST  
 S56°W EAST N74°W  
 41.30' 33.0' (TO FACE) 78.35'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 10/10/93  
 Surveyor's Michigan License No. 16926