

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Delta COUNTY  
T 40 N R 18 W

DESCRIPTION OF CORNER Section corner for sections  $\frac{28}{27}$   $\frac{33}{34}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11/5/70 F. J. Bray

WITNESSES TO CORNER..... 10" Cedar (S. 33) (NBT) S 80° W, 3.7'



6" Cedar (S. 27) (NBT) N 73° E, 2.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from woodpost in proper bearing and distance from possible original B.T., Cedar stump with axe marks, stump in poor condition. Corner checks fairly well with swamp edges and  $\frac{1}{4}$  corner to the North.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray  
REGISTERED LAND SURVEYOR  
Frank J. Bray

DATE

12-2-70

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68