

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES



LAND CORNER RECORD


Delta COUNTY
T 40 N R 18 W

DESCRIPTION OF CORNER Section corner for sections $\frac{11}{12}$
 $\frac{14}{13}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11/18/70 F. J. Bray with F. Finlay

WITNESSES TO CORNER..... 11" R. Maple (S. 11) (NBT) N 19° W, 9.0'



5" R. Maple (in clump) (S. 12) (NBT) N 53° E, 5.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by proportioning distance between section corner 1 mile to east and to west and to check with stream crossing to north and land features to south. No original evidence found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 12-7-70
REGISTERED LAND SURVEYOR
Frank J. Bray

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68