

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Delta COUNTY


T 40 N R 18 W

DESCRIPTION OF CORNER Section corner for sections ^{10/11} 15/14

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9/29/70, F. J. Bray with McDonald and Finlay

WITNESSES TO CORNER..... 5" W. Birch (S.14) (NBT) S 82° E, 6.6'



9" W. Birch (S.15) (NBT) S 58° W, 11.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed the proportioned distance to section corners to north and to south and the proportioned distance between section corner to the west and stream crossing to the east. Stream crossing to the north checks fairly well. Axe marks on cedar stump near.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

11/5/70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68