

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Delta COUNTY
40
T 39 N R 18 W

DESCRIPTION OF CORNER Section corner for sections $\frac{33}{4}$ T40N, R18W
 $\frac{4}{3}$ T39N, R18W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11/5/70 F. J. Bray

WITNESSES TO CORNER..... 10" Cedar (S. 33) (NBT) N 72° W, 9.3'



8" Hemlock (S. 34) (NBT) N 88° E, 21.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by placing on line at the single proportioned distance between section corner 1 mile to west and $\frac{1}{4}$ corner $2\frac{1}{2}$ miles to east. Old down fence corner southwest approximately $\frac{1}{2}$ chain. Old blazes found on east and west line check well.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE 12-3-70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68