

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Delta COUNTY
40
T 39 N R 18 W

DESCRIPTION OF CORNER Section corner for sections 2/1 T39N, R18W
35/36 T40N, R18W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11/10/70 F. J. Bray

WITNESSES TO CORNER..... 6" Cedar (S. 2) (NBT) S 88° W, 19.1'



6" W. Birch (S. 1) (NBT) S 52° E, 6.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by placing on line and the single proportioned measurement between section corner 1 mile to west and $\frac{1}{4}$ corner $\frac{1}{2}$ mile to east.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

12-7-70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68