

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Delta COUNTY
40
T 39 N R 18 W

DESCRIPTION OF CORNER Section corner for sections 34/35 T40N, R18W
3/2 T39N, R18W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/6/70 F. J. Bray

WITNESSES TO CORNER..... 7" W. Birch (S. 34) (NBT) N 31° W, 26.6'



5" W. Birch (S. 35) (NBT) N 39° E, 21.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by placing the single proportioned measurement and on line between section corner 1 mile to west and $\frac{1}{4}$ corner $1\frac{1}{2}$ miles to east. No original evidence found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

12-7-70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68