

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40 N.R. 18 W


Delta COUNTY

DESCRIPTION OF CORNER Closing Corner for Sections 1 and 2 on 4th Correction Line.

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 1/18/61 with Bill Wallace and Art Enger.

WITNESSES TO CORNER... 9" W. Spruce (C C S 1 NBT) S 42° E 29 Links



8" Cedar (C C S 2 NBT) S 55° W 37½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Hemlock B.T. bearing S 55° W, 25 Links. B.T. down and in poor condition. Found Yellow Birch Corner Tree, a stub about 4' high.

Note: This corner lies 3.15 chains west of 1/4 corner, Section 31, T41N, R18W.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE July 21, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler