

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Delta COUNTY  
T 40 N R 18 W

DESCRIPTION OF CORNER 1/4 corner for sections 15/14

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9/30/70, F. J. Bray

WITNESSES TO CORNER..... 7" L. Pine (1/4 S) (NBT) N 36° W, 19.4'



5" Hemlock (1/4 S) (NBT) S 65° E, 7.1'

Down squared cedar stub. S 77° W, 4.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway between section corners and to the west of a straight line to make swamp edges to the north and to the south check fairly well with the original field notes. Down squared cedar stub near.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 11/5/70  
REGISTERED LAND SURVEYOR  
Frank J. Bray

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68