

**SURVEY & REMONUMENTATION**

FEB 02 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On December 30, 1998

*Walter C. Thomas*  
Chairman

For corners in  
DELTA  
(County)

Located In: Corner Code #

- |                                    |                             |                      |
|------------------------------------|-----------------------------|----------------------|
| 1. Public Land Survey              | T <u>40</u> N R <u>19</u> W | <u>B-1 &amp; B-3</u> |
|                                    | T _____ R _____             | _____                |
|                                    | T _____ R _____             | _____                |
|                                    | T _____ R _____             | _____                |
| 2. Property Controlling in Section | S _____ T _____ R _____     | _____                |
|                                    | S _____ T _____ R _____     | _____                |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____     | _____                |
|                                    | S _____ T _____ R _____     | _____                |

Recorded Jan 4 1999  
3:40 PM  
9 117  
*Walter C. Thomas*  
Chairman

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims B-1 [1/4 COR SEC 1] B-3 [1/4 COR SEC 7]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on DECEMBER, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1 [1/4 COR SEC. 1] NOT SET IN ORIGINALS  
NO RECORD OF SUBSEQUENT CORNER ESTABLISHMENT

B-3 [1/4 COR SEC. 7] A.MERRYWEATHER, D.S. - 1848 - HEMLOCK 20" CORNER TREE (W.PINE 16"-N65°E-23 LINKS)  
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY AND/OR RESTORATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 [1/4 COR SEC. 1] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION AT MIDPOINT BETWEEN AND ON LINE WITH SECTION CORNERS 1/2 MILE EAST & WEST.

B-3 [1/4 COR SEC 7] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION AT MIDPOINT BETWEEN AND ON LINE WITH SECTION CORNERS 1/2 MILE EAST & WEST.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 SET BERNTSEN ALNB30 ALUM MONUMENT W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.  
CEDAR 12" SPRUCE 05" CEDAR 06" SPRUCE 07" SURVEY MONUMENT SIGN POST  
N57°W N10°E S56°E S71°W SOUTH  
22.90' 40.90' 27.62' 25.60' 1.81' (TO FACE)

B-3 SET BERNTSEN ALNB30 ALUMN MON. W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.  
HEMLOCK 12" HEMLOCK 10" HEMLOCK 12"(TWIN) Y.BIRCH 11"" SURVEY MONUMENT SIGN POST  
N30°E S30°E S31°W N72°W NORTH  
28.63' 14.62' 13.71' 28.66' 1.30' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/23/98

Surveyor's Michigan License No. 16926