

FEB 02 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On December 30, 1998
Chairman

For corners in

DELTA

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 40 N R 19 W D-5
T 40 N R 19 W D-7
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R

Recorded Jan 4 1999
3:40 PM
9 120
Walter C. Thorne

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims
D-5 [N1/4 COR SEC 17] D-7 [N1/4 COR SEC 20]

Grid with columns A-M and rows 2-13. Contains numerical data points for survey locations.

I, M.P. DAVIS, in a field survey on DECEMBER, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-5 [N1/4 COR SEC. 17] A.MERRYWEATHER, D.S. - 1848 - WOOD POST - (BIRCH 06" S27°E 07 LINKS) (HEMLOCK 10" N51°W 22 LINKS) NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY AND/OR RESTORATION
D-7 [N1/4 COR SEC 20] A.MERRYWEATHER, D.S. - 1848 - WOOD POST (SOFT MAPLE 08" S40°W 40 LINKS) (SPRUCE 08"-EAST-150 LINKS) NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY AND/OR RESTORATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-5 [N1/4 COR SEC. 17] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION AT MIDPOINT BETWEEN AND ON LINE WITH SECTION CORNERS 1/2 MILE EAST AND WEST. THE CORNER POSITION FALLS ON THE SIDE SLOPE OF THE LEFT BANK OF THE STURGEON RIVER. A REFERENCE MONUMENT WAS THEREFORE SET ON THE E-W SECTION LINE 74.0 FEET EAST OF THE CORNER POSITION.
D-7 [N1/4 COR SEC 20] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION AT MIDPOINT BETWEEN AND ON LINE WITH SECTION CORNERS 1/2 MILE EAST & WEST. THE CORNER IS LOCATED IN RELATIVE OPEN MARSH LAND AND IN A SHALLOW BEAVER FLOODING MAKING A COMPARISON DISTANCE TO THE "GLO" CALL FOR THE STREAM X-ING TO THE EAST DIFFICULT, HOWEVER AS NEARLY AS COULD BE DETERMINED THIS POSITION FITS WELL WITH THE "GLO" CALL.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-5 (REF. MON) SET BERNTSEN A1NB30 ALUM MONUMENT W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.
HEMLOCK 08" MAPLE 08" SURVEY MONUMENT SIGN POST
S62°E S07°W NORTH
19.10' 28.20' 1.65' (TO FACE)
D-7 SET BERNTSEN A1NB30 ALUMN MON. W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.
MAPLE 11" SURVEY MONUMENT SIGN POST
N10°E SOUTH
15.26' 1.51' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/23/98
Surveyor's Michigan License No. 16926