

**SURVEY &
REMONUMENTATION**

OCT 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On June 6, 1995

Walter C. Thomas
Chairman

For corners in

DELTA (County)	Located In:	Corner Code #
1. Public Land Survey	T 40 N - R 19 W -	<u>F-7 & F-9</u>
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Recorded 11/13/1995

9:00 o'clock A.M. in Liber 8 Page 68

Walter C. Thomas Reg. of Deeds.
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

F-7 [N1/4 COR SEC 21] F-9 [S1/4 COR SEC 21]

I, W.P. DAVIS, in a field survey on DECEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-7 [N1/4 COR SEC. 21] A.MERRYWEATHER, D.S. - 1848 - WOOD POST (WILLOW 06°-NORTH-08 LINKS) (SPRUCE 06°-550°E-06 LINKS)
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY OR MONUMENTATION
- F-9 [S1/4 COR SEC. 21] A.MERRYWEATHER, D.S. - 1848 - WOOD POST (OAK 37°-N48°E-09 LINKS) (W.PINE 24°-S70°W-90 LINKS)
D.A.BORTHERTON-1910-ID CORNER POSITION FROM STUMP OF GLO CAK BT & REMAINS OF W.PINE BT-SET NEW STAKE NO WIT'S NOTED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-7 [N1/4 COR SEC. 21] RESTORED CORNER POSITION AT MIDPOINT BETWEEN SECTION CORNERS EAST AND WEST NO EVIDENCE OF ORIGINAL CORNER OR ACCESSORIES FOUND.
- F-9 [S1/4 COR SEC. 21] FOUND IN PLACE A 1" IRON PIPE, IDENTIFIED SAME FROM THE SUPERVISOR'S PLAT NO. 1 OF NAHMA TOWNSHIP AS RECORDED IN LIBER "B" OF PLATS ON PAGES 82 & 83. NO OTHER EVIDENCE FOUND. ACCEPTED EXISTING MONUMENT AS THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-7 SET BERNTSEN AINB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION.
CEDAR 08" TAMRACK 04" CEDAR 04" CEDAR 06" SURVEY MONUMENT SIGN POST
N47°E N65°W S39°W S50°E NORTH
22.63' 21.98' 10.85' 28.29' 2.83' (TO FACE)
- F-9 SET OVER EXISTING MONUMENT, A BERNTSEN AINB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION.
MAPLE 15" MAPLE 10" MAPLE 12" NOTE: CORNER POSITION IS LOCATED IN RESIDENTIAL
S87°W S87°E S15°W YARD NO SIGN POST SET.
2.10' 6.60' 29.30'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by W.P. Davis Date 4/13/95

Surveyor's Michigan License No. 16926

