

OCT 26 1995

COMMISSION

For corners in

DELTA  
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 40 W R19 W H-1 & H-3  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims H-1 [N1/4 COR SEC 3] H-3 [N1/4 COR SEC 10]

I, M.P. DAVIS, in a field survey on DECEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- H-1 [N1/4 COR SEC. 3] NOT ESTABLISHED IN ORIGINALS  
M.S. McNABE - 1919 - ESTABLISHED ON CORRECTION LINE 331' EAST OF SW COR SEC 36 T41N, R19W-SET IRON-POPPLE-89°W-31.5' & POPPLE-N10°W-41.3'
- H-3 [N1/4 COR SEC. 10] A.MERRYWEATHER, D.S. - 1848 - WOOD POST (BIRCH 15°-S80°E-06 LINKS) (BALSAM 08°-N50°W-17 LINKS)  
M.S. McNABE-1913-CORNER FENCE POST CLAIMED BY SETTLERS TO HAVE BEEN SET FROM ORIGINALS-488' SOUTH OF HWY 2-NO OTHER WIT'S NOTED  
M.S. McNABB-1919-ID CORNER POSITION BY EXISTING CORNER FENCE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-1 [N1/4 COR SEC. 3] FOUND IN PLACE & 331' EAST OF A FARM FENCE LINE TO THE NORTE A 1/2" IRON PIN BENT AND IN POOR CONDITION FROM ROAD IMPROVEMENTS. NO EVIDENCE OF McNABB'S POPPLE WITNESS TREES FOUND. ACCEPTED EXISTING MONUMENT AS THAT ESTABLISHED BY McNABB.
- H-3 [N1/4 COR SEC. 10] FOUND IN PLACE, AT THE JCT. OF ANCIENT FARM FENCES N-S & E-W, AN IRON BOLT. NO EVIDENCE OF McNABB'S Y. BIRCH BT FOUND. ACCEPTED EXISTING MONUMENT AS BEING A CAREFULL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-1 REPLACED, 6" BELOW RD SURFACE, EXISTING MONUMENT W/A 5/8" X 18" REBAR W/A 3" ALUMN CAP STAMPED TO ID THE CORNER POSITION.  
BASSWOOD 10" CEDAR 7" W. BIRCH 10" SURVEY MONUMENT SIGN POST  
S17°E N10°W S38°W NORTH  
48.28' 31.96' 45.70' 14.62' (TO FACE)
- H-3 REPLACED EXISTING MON W/A 4" X 4" X 36" CONC. MON. W/A 3" BRASS CAP STAMPED TO ID THE CORNER POSITION.  
SPRUCE 8" RED PINE 9" SURVEY MONUMENT SIGN POST NOTE: NO OTHER WIT'S AVAILABLE. CORNER POSITION SURROUND BY  
S26°W N06°E WEST FARM FIELDS.  
17.13' 10.40' 2.40' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 4/13/95

Surveyor's Michigan License No. 16926

Approved by Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On June 6, 1995  
Robert Schmelzer  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Recorded JUN 13 1995  
9:00 o'clock A.M. in Liber 8 Page 65  
William C. Thorne Reg. of Deeds.  
Delta County, Michigan  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							