

OCT 26 1995

COMMISSION

Approved by Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On June 6, 1995
W. H. Helmsling
Acting Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in DELTA (County)

Located In: Corner Code #

- 1. Public Land Survey T40 N R19 W I-3 & I-4
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in-Sec. S T R

Recorded IN 13 1995
at 9:00 o'clock A.M. in Liber 8 Page 58
Walter C. Thorne Reg. of Deeds.
Delta County, Michigan
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims I-3 [NW COR SEC 11] I-4 [W1/4 COR SEC 11]


A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, M.P. DAVIS, in a field survey on JANUARY, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
I-3 [NW COR SEC. 11] A. MERRYWEATHER, D.S. - 1848 - WOOD POST (SUGAR 07°E-S30°W-18 LINKS) (HEMLOCK 08°-N15°E-18 LINKS)
M.S. McNABB - 1920 - FOUND STAKE IN PLACE AT CORNER FENCE POST NORTH & EAST & WEST
- I-4 [W1/4 COR SEC. 11] A. MERRYWEATHER, D.S. - 1848 - WOOD POST (CEDAR 08°-N33°E-08 LINKS) (CEDAR 08°-S75°W-07 LINKS)
M.S. McNABB-1920-ESTABLISHED FROM GLO CEDAR BY NE-SET STAKE - CEDAR 12°-N65°W-28.8' & CEDAR 12°-S20°E-10.0'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I-3 [NW COR SEC. 11] NO EVIDENCE OF STAKE IN PLACE AS NOTED BY McNABB IN 1920. RESET CORNER POSITION AT JCT. OF ANCIENT FENCE LINES N-S & E-W AS PER THE RECORDS OF McNABB. ACCEPTED THIS POSITION AS THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.
- I-4 [W1/4 COR SEC. 11] FOUND IN PLACE McNABB'S 1920 SCRIBED WOOD POST & NW CEDAR BT (STILL GREEN). NO EVIDENCE OF THE "GLO" CEDAR BT MENTIONED IN McNABB'S RECORDS FOUND AS IT HAS APPARENTLY BEEN DESTROYED DURING CONSTRUCTION OF E-W WOODS ROAD. ACCEPTED EXISTING MONUMENT AS A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-3 SET 4" X 4" X 36" CONCRETE MONUMENT W/A 3" BRASS CAP STAMPED TO ID THE CORNER POSITION.
MAPLE 9" S14°E 35.70'
MAPLE 13" S85°W 54.95'
ASH 7" N44°E 36.73'
SURVEY MONUMENT SIGN POST SOUTH 1.66' (TO FACE)
- I-4 SET BERNTSEN A1NB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION.
MAPLE 8" S22°E 32.49'
CEDAR 6" S27°W 24.92'
HEMLOCK 16" N35°E 28.15'
CEDAR 24" N65°W 30.20'
SURVEY MONUMENT SIGN POST EAST 2.32' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 4/13/95
Surveyor's Michigan License No. 16926