

SURVEY & REMONUMENTATION

OCT 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On June 6, 1995
Michael Delaney
 Acting Chairman

For corners in DELTA
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	40 N	R	19 W	<u>K-1 & K-2</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Recorded JUN 13 1995
 at 9:00 o'clock A.M. in Liber 8 Page 69
Walter C. Thomas Reg. of Deeds,
 Delta County, Michigan
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims K-1 [NW COR SEC 1] K-2 [W1/4 COR SEC 1]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	2						
5												
6	18	17	16	15	14	3						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on JANUARY, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 K-1 [NW COR SEC. 1] A. MERRYWEATHER, D.S. - 1848 - WOOD POST (BLACK ASH 08'-S40'E-05 LINKS) (CEDAR 09'-S43'W-13 LINKS) M.S. McNABB - 1920 - 1D CORNER POSITION FROM ORIGINAL BT'S - SET IRON STAKE & POST BT STAKES SE & SW 33'
 K-2 [W1/4 COR SEC. 1] A. MERRYWEATHER, D.S. - 1848 - WOOD POST (CEDAR 12'-S36'W-16 LINKS) (CEDAR 10'-N50'E-22 LINKS) M.S. McNABB-1920-FOUND STAKE SET PREVIOUSLY "BETWEEN CORNERS"- SET IRON - COR FENCE POST-N70'W-17.8 & FENCE POST-S60'W-21.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 K-1 [NW COR SEC. 1] FOUND IN PLACE A LEAF SPRING & ROTTED REMAINS OF A WOOD POST. NO EVIDENCE OF McNABB'S "BT" STAKES OR THE "GLO" BT'S. CORNER IS LOCATED IN ANCIENT E-W FARM FENCE AND CHECKS WITH McNABB'S DISTANCE WEST TO THE S1/4 COR OF SEC 31 T41M R18W. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

K-2 [W1/4 COR SEC. 1] FOUND IN PLACE A 3/4" I.P. THIS MONUMENT CHECKS WELL WITH BEING PROPORTIONATE DISTANCE BETWEEN & ON LINE WITH CORNERS TO THE NORTH & SOUTH. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 SET, OVER EXISTING MONUMENT, A BERNTSEN A1NB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION.
 ASH 8" SURVEY MONUMENT SIGN POST NOTE: IN OLD FARM AREA, NO OTHER WIT'S AVAILABLE
 S08'E EAST
 21.90' 2.12' (70 FACE)

K-2 SET, OVER EXISTING MONUMENT, A BERNTSEN A1NB30 ALUMN MON. W/A 3-1/4" CAP STAMPED TO ID THE CORNER POSITION.
 N-S FARM FENCE FARM FENCE WEST CROSS ON STONE SURVEY MONUMENT SIGN POST NOTE: CORNER IS IN OPEN PASTURE LAND. NO OTHER WIT'S AVAILABLE
 WEST NORTH N80'W WEST
 15' 9' 63.41' 19.58' (70 FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 4/13/95
 Surveyor's Michigan License No. 16926