

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 40 N.R.'s 19 & 20W


Delta COUNTY

DESCRIPTION OF CORNER Section corner for sections T40N, R20W  $\frac{1}{6}$  12/7 T40N, R19W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6/21/68, F. J. Bray

WITNESSES TO CORNER..... 12" W. Pine (S.6) (NBT) N 78° E, 117½ links



7" B. Spruce (S.12) (NBT) S 57° W, 36 links

5" B. Spruce (S. 1) (NBT) N 39° W, 24 links

AND

CIRCLE CORNER REGISTERED

### DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from down wood stake. Point of old rotted post found under moss and earth. Blazed trees facing corner. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/11/68  
REGISTERED LAND SURVEYOR  
Frank J. Bray