

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 40N N.R.'s 19 & 20 W


Delta COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections T40N, R20W 1/6 T40N, R19W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6/21/68, F. J. Bray

WITNESSES TO CORNER..... 6" J. Pine (1/2S) (NBT) N 63° W, 15 links



9" J. Pine (1/2S) (NBT) S 66° E, 11 links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between section corners 1/2 mile to north and to south. Stream crossing to south checks fairly well. Small wood post near. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/11/68
REGISTERED LAND SURVEYOR
Frank J. Bray