

**SURVEY &
REMONUMENTATION**

FEB 18 1994

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1980 On Jan. 20, 1994

M. P. Davis
Acting Chairman

For corners in COMMISSION
DELTA
(County)

Located In: Corner Code ≠#

1. Public Land Survey	T	<u>40 N</u>	R	<u>22 W</u>	<u>B-9</u> & <u>C-9</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Recorded January 21, 1994

at 9:00 o'clock a.m. in Lib. 7 Page 354

William C. Thomas Reg. of Deeds,
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
[B-9] N1/4 COR SEC 30 [C-9] NW COR SEC 29

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-9 [N1/4 COR SEC 30] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (CEDAR 8"-S60°E-5 LINKS) (TAMERAC 8"-N60°W-13 LINKS)
D.A. BROTHERTON - 1895 - NO EVIDENCE OF ORIGINALS - ESTABLISHED COR 1/2 DISTANCE BETWEEN COR'S - NO WITS NOTED

C-9 [NW COR SEC 29] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (SPRUCE PINE 7"-N30°W-30 LINKS) (SPRUCE PINE 7"-S15°E-1.24 CHS)
D.A. BROTHERTON - 1895 - ID COR POSITION FROM ORIGINALS (NOW BOTH BURNT STUMPS) SET NEW POST (BLACK OAK 5"-N52 1/2°E-69') (TELEGRAPH POLE-S69°E-50.3') (TELEGRAPH POLE-S81°50'W-103.2')
M.S. McNABB - 1948 - FOUND WOOD POST & IRON STAKE - ID FROM BROTHERTON BT'S - NEW BT'S NOTED (OAK 20°N55°E-72') (OAK 8°-S55°E-83.4') (TEL POLE-S20°W-8.5')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9 [N1/4 COR SEC 30] FOUND, 30' M. OR L. SOUTH OF COUNTY ROAD CENTER LINE, A 2" IP @ MID POINT BETWEEN SEC COR'S FOUND EAST & WEST ACCEPTED EXISTING MON AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL COR.

C-9 [NW COR SEC 29] FOUND, 29' M. OR L. NORTH OF COUNTY ROAD CENTER LINE, AN IRON PIN & POINTED REMAINS OF A WOOD STAKE - ID COR POSITION FROM McNABB'S OAK BT (N55°E-72') WHICH IS STILL GREEN ACCEPTED EXISTING MON AS A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL COR.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9 SET, OVER EXISTING MON, A BERNTSEN A1NB30 ALUMN MON W/A CAP STAMPED TO ID THE CORNER POSITION
TAMARACK 12" TAMARACK 10" TAMARACK 15" SURVEY MONUMENT SIGN POST
N6°E S35°E S38°W SOUTH
85.35' 74.33' 69.25' 2.68' (TO FACE)

C-9 SET, OVER EXISTING MON, A BERNTSEN A1NB30 ALUMN MON W/A CAP STAMPED TO ID THE CORNER POSITION
OAK 10" JACK PINE 7" OAK 15" SURVEY MONUMENT SIGN POST
N59°W N55°E S30°E NORTH
21.82' 26.06' 81.60' 1.69' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED

Signed by M.P. Davis Date 1/15/93
Surveyor's Michigan License No. 16926