

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1999 On Jan 20, 1994
Robert B. Schulz
 Acting Chairman

For corners in

DELTA
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|------------------|
| 1. Public Land Survey | T <u>40</u> N R <u>22</u> W | <u>(C-2) I-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded January 21, 1994

at 9:00 o'clock a.m. in Lib 7 Page 351

Walter C. Thum Reg. of Deeds.
 Delta County, Michigan
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
[C-2] W1/4 COR SEC 5 [I-1] NW COR SEC 2]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-2 [W1/4 COR SEC 5] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (SOFT MAPLE 7"-S10°E-68 LINKS) (HEMLOCK 22"-N20°W-5 LINKS)
 M.S. McNABB - 1932 - ID CORNER POSITION BY I.P. FOUND IN PLACE-NEW BT'S NOTED SOFT MAPLE 7"-S47°W-41.3' & COR FENCE POST N50°W-25.2'
- I-1 [NW COR SEC 2] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (SOFT MAPLE 10"-S40°E-12 LINKS) (CEDAR 12"-S43°W-30 LINKS)
 M.S. McNABB - 1917 - ID CORNER POSITION FROM ORIGINAL CEDAR BT (DOWN-SCRIBE MARKS STILL PLAIN) SET NEW STAKE & BT'S DOUBLE POPLAR STUMP S45°E-19.8' & ASH 4"-S50°W-36.8'
 M.D.O.T. (DATE UNKNOWN) FOUND SQ'D CEDAR POST IN PLACE - BT'S NOTED (ASH 5" S50°W-6.5') (POPLAR 12"-NORTH-23.0') (CEDAR 4"-S74°E-8.25)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-2 [W1/4 COR SEC 5] FOUND 1-1/4" I.P. IN EAST-WEST COUNTY ROAD 9' NORTH OF C.L. FROM WHICH A MAPLE (NOW 17") BEARS S47°W-41.3'-McNABB'S DISTANCE TO C.L. OF HWY M-35 ALSO CHECKS WELL FROM THIS MONUMENT. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
- I-1 [NW COR SEC 2] FOUND 5/8" REBAR IN CENTER LINE MEDIAN OF HWY. U.S. 2 & 41, ID CORNER POSITION FROM M.D.O.T. CONSTRUCTION PLANS FOR HWY U.S. 2 & 41 - ACCEPTED SAME AS BEING A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-2 SET INSIDE EXISTING I.P. A 5/8" X 18" REBAR W/A 3-1/4" ALUM CAP STAMPED TO ID COR POSITION & RAISED TO RD SURFACE W/A MON BOX
- | | | | |
|------------|-----------|-------------|-----------|
| POWER POLE | MAPLE 17" | ANCHOR POLE | MAPLE 17" |
| N39°W | N46°E | S9°W | S47°W |
| 30.13' | 73.16' | 39.22' | 41.3' |
- I-1 SET 3-1/4" ALUMN CAP STAMPED TO ID COR POSITION OVER REBAR & RAISED TO GROUND LEVEL W/A MON BOX
 NO WIT'S NEAR AS COR POSITION IS LOCATED IN C.L. MEDIAN OF 4 LANE HWY (U.S. 2 & 41)
 SURVEY MON SIGN POST - N33°E-2.54' (TO FACE)
 CORNER POSITION IS LOCATED AT HWY STA 842+83.5

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED

Signed by M.P. Davis Date 12/30/93

Surveyor's Michigan License No. 16926