

FEB 18 1994

COMMISSION

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On Jan. 20, 1994  
Robert E. Schenkel Acting Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 40 N R 22 W D-9 & E-6
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Recorded January 21, 1994  
at 9:00 o'clock a.m. in Liber 7 Page 360  
Walter C. Zimm Reg. of Deeds,  
Delta County, Michigan  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_  
[D-9] N1/4 COR SEC 29 [E-6] W1/4 COR SEC 16

I, M.P. DAVIS, in a field survey on NOVEMBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
  - D-9 [N1/4 COR SEC 29] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (NORWAY PINE 20°-N42°E-30 LINKS) (WHITE PINE 20°-S52°W -29 LINKS); JAMES M. BARKER, SURVEYOR - 1887 - REFERENCE PLAT OF SOUTH GLADSTONE LIBER "A" OF PLATS PAGE 15 - NOT WITS NOTED
  - D.A. BROTHORN - 1895 - ID CORNER POSITION FROM BURNT STUMPS OF BOTH ORIGINALS - NEW BT'S (TELE POLE S52°E-21.6) (IRON HUB-S24°E-44.6')
  - M.S. McNABB - 1931 - ID COR POSITION FROM WOOD STAKE & PLAT OF SOUTH GLADSTONE - SET IP IN CONC MON - NEW BT'S (OAK 10°-N63°W-79.8') (OAK 10°-N5°E-37')
  - E-6 [W1/4 COR SEC 16] WOOD POST-WOOD POST - A. MERRYWEATHER, D.S. - 1846 (W.PINE 28°-N66°E-49 LINKS) (NORWAY PINE 26°-S45°W-1.37 CHS. M.S. McNABB - 1925 - IRON STAKE IN PLACE - NO WIT'S OR DESCRIPTION OF THE ORIGIN OF THE MON FOUND MENTIONED IN McNABB'S NOTES
  - GEORGE NAULT-RLS 6521 [FOR M.D.O.T.] - 1971-FOUND AXEL SHAFT IN PLACE-NEW BT'S (CHERRY 14°-N40°E-35.7') (OAK 12°-S80°E-24.07')
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
  - D-9 [N1/4 COR SEC 29] FOUND THIS DATE McNABB'S CONC MON - ID COR POSITION FROM PLAT OF MASHEK-BUCKBEE ADDITION TO GLADSTONE-REC'D LIBER "B" OF PLAT PAGE 57 - ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
  - E-6 [W1/4 COR SEC 16] FOUND THIS DATE AXEL SHAFT AS DESCRIBED IN M.D.O.T. RECORDS - ACCEPTED EXISTING MONUMENT AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
  - D-9 SET, OVER EXISTING MON, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID COR POSITION & RAISED TO RD SURFACE W/A MON BOX
 

OAK 26'	POWER POLE	OAK 15'	JACK PINE 7"
N12°W	N73°E	S48°E	S18°W
75.42'	81.62'	101.85	58.20'
  - E-5 SET, OVER EXISTING MON, A BERNTSEN AINB30 ALUMN MON W/A CAP STAMPED TO ID THE COR POSITION
 

OAK 12'	JACK PINE 13'	CONC. MON.	SURVEY MONUMENT SIGN POST
N32°E	S17°E	EAST	WEST
66.97'	65.38'	33.0'	2.98' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED

Signed by M.P. Davis Date 11/15/93  
Surveyor's Michigan License No. 16926